

15-051-20859-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JAN 5 1973

CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Jet Drilling Company & Zetco Petroleum

Complete Address 514 One Twenty Building Wichita, Kansas

Lease Name Sisters of St. Agnes Well No. 2

Location SW NE NW Sec. 20 Twp. 11 Rge. (E) (W) 16

County Ellis Total Depth 3363'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 10:45 A Day 3<sup>rd</sup> Month 3<sup>rd</sup> Year 1973

The above well was plugged as follows:

RTD 3363' 8 5/8 csg set at 261' cwc. Cmt. Mat. 50-50 poz cmt W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 50 sk  
cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 25 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Murray  
Well Plugging Supervisor

INVOICED

DATE 1/9/73  
INV. NO. 6830-W