



15-105-00015-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

VERBAL PERMIT FORM

(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 12 1962

09-13-1962
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date September 9, 1962, authorized
the following plugging operation:

Operator's full Name: Donald T. Ingling & Walting
Complete Address: 615 First Natl. Bank Bldg., Wichita 2, Kansas
Lease Name: Olsen Well No. 1
Location: NW NW SE Sec. 11 Twp. 13 Rge. 8 (E) (W)
County Lincoln Total Depth 3827'
Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Circulate heavy mud. Fill hole with mud to 370'. Set
rock bridge from 370' to 360' and cement with 20 sacks
thru drill pipe. Fill hole with mud to 35'. Push plug
and 1/4 sack hulls to 35' and cement with 10 sacks.
Bridge, and cement rathole with 2 sacks.

Very truly yours,

Stilwell J. Leonard
Conservation Division Agent