



GEORGE DOCKING Governor
 MARION BEATTY Chairman
 HARRY G. WILES Commissioner
 RICHARD C. BYRD Commissioner
 RAYMOND B. HARVEY Secretary
 CLYDE E. MILLIGAN Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS
 JEWEL M. OGDEN, Director

Jewel M. Ogden, Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

I have this date November 24, 1958, authorized the following plugging operation:

Operator's Full Name: Kewanee Oil Co.

Complete Address: P.O. Box 2093, Wichita 1, Kansas

Lease Name: Rahmeir Well No. 1

Location: NW-NW-SE Sec. 8 Twp. 13 Rge. 9 (E) (W) x

County: Lincoln Total Depth: 4030

Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D & A x

Other well as hereafter indicated: _____

Operator was instructed to plug well as follows:

Gun pits and circulate heavy mud. Fill hole to 300' with heavy
mud--push plug and 1/2 sack hulls to 300' and cement with 20 sacks
thru drill pipe. Fill hole to 40' with heavy mud--push plug and
hulls to 40' and cement with 10 sacks. Bridge, and cement rathole
with 2 sacks.

Very truly yours,

Signed: William J. Loman
 Conservation Division Agent

RECEIVED
 STATE CORPORATION COMMISSION

DEC 2 - 1958
 12-12-1958
 CONSERVATION DIVISION
 Wichita, Kansas