

State of Kansas



15-105-20010-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

August 30, 1979

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Kent Longhoffer of Emphasis Oil Operations has this date requested permission to plug the following described well:

Mr. Longhoffer guarantees payment of the plugging fee.

Operator's full Name: Terra Resources, Inc.

Complete Address: P.O. Box 839, Oklahoma City, Oklahoma 73101

Lease Name: Etzold Well No. 1

Location: SW SW NE Sec. 18 Twp. 13 Rge. 9 (E) (W) X

County: Lincoln Total Depth 3670' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Longhoffer was instructed to plug the well as follows:

8 5/8" - 482' cement circ. Fill hole with mud. Pump
50 sacks cement at 480' (through drill pipe). Push plug
and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole and cement with
cement.

RECEIVED
CORPORATION DIVISION
09-06-1979
SEP - 6 1979

Very truly yours, CONSERVATION DIVISION
Wichita, Kansas

William J. Tomer
Conservation Division Agent