



15-105-20013-00-00

JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
245 North Water  
WICHITA, KANSAS 67202

September 23, 1981

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Ervin Neighbors of Lobo Drilling, Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Reif Oil Operations

Complete Address: Box 298, Hoisington, Kansas 67544

Lease Name: Kottman Well No. 1

Location: C NE SE Sec. 34 Twp. 13 Rge. 9 (W)

County: Lincoln Total Depth: 3750'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Neighbors was instructed to plug the well as follows:

8 7/8" - 361' - 220 sacks - 60/40 circ. Anhydrite 481-491

Circulate hole and fill with mud. Pump 50 sacks cement through drill pipe at 480'. Fill hole with mud to 40'. Push plug and

1/2 sack hulls to 40' and cap hole with 10 sacks cement.

Cement rat hole with 10 sacks cement.

RECEIVED  
STATE CORPORATION COMMISSION

Very truly yours,

Arthur J. Coman  
Conservation Division Agent

SEP 28 1981  
09-28-1981  
CONSERVATION DIVISION  
Wichita, Kansas