

State of Kansas



15-105-20008-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

November 20, 1978

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1978
11-27-1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Wayne Dolezal of Terra Resources, Inc. has this date requested permission to plug the following described well:

Mr. Dolezal guarantees payment of the plugging fee.

Operator's full Name: Terra Resources, Inc.

Complete Address: P.O. Box 839, Oklahoma City, Oklahoma

Lease Name: Homeier Well No. 1

Location: E/2 SE NE Sec. 14 Twp. 13 Rge. 10 (E) (W) X

County: Lincoln Total Depth 4200' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Dolezal was instructed to plug the well as follows:

8 1/8" - 453' - 185 Sacks - cem. circ. Fill hole with mud.
Ramp 50 Sacks cement through drill pipe at 450'
Fill hole with mud to 40' Push plug and 1/2 sack
balls to 40' and cap hole with 10 sacks cement.
Bridge rat hole and cement with 2 sacks cement.

Very truly yours,

[Signature]
Conservation Division Agent