



15-105-20003-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg.
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 15 1968
 CONSERVATION DIVISION
 Wichita, Kansas
 11-15-1968

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

November 12, 1968

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ed Weiler of Shields Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Weiler guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Kansas

Lease Name: Rezabek Well No. 1

Location: SE SE SE Sec. 20 Twp. 13 Rge. 10 (E) (W) X

County: Lincoln Total Depth 3574' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Weiler was instructed to plug the well as follows:

Fill hole with heavy mud. Push plug to 400'. Cement hole with 25 sacks
cement through drill pipe at 400'. Pump 25 sacks cement through drill
pipe at 150'. Push plug and 1/4 sack hulls to 40'. Cap hole with 10
sacks cement. Bridge rathole and cement with 2 sacks.

Very truly yours,

Conservation Division Agent