



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1963
09-18-1963
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Ralph McNutt of Donald T. Ingling has this date requested permission to plug the following described well:

Mr. McNutt guarantees payment of the plugging fee.

Operator's full Name: Donald T. Ingling

Complete Address: 615 First Nat'l Bank Bldg., Wichita, Kansas

Lease Name: Meyer Well No. 1

Location: NW NW Sec. 17 Twp. 13 Rge. 10(E) (W) X

County Lincoln Total Depth 3763' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. McNutt was instructed to plug the well as follows:

Circulate heavy mud. Fill hole with mud to 300'. Set rock bridge from 300' to 290' and cement hole with 20 sacks through drill pipe. Fill hole with mud to 35'. Set bridge from 35' to 30' and cap hole with 8 sacks cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

[Signature]
Conservation Division Agent