

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission
CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 18 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burriss of Tilco et al has this date requested permission to plug the following described well:

Mr. Burriss guarantees payment of the plugging fee.

Operator's full Name: Tilco etal

Complete Address: 200 Sutton Place, Wichita, Kansas

Lease Name: Evans Well No. 1

Location: C NE SE Sec. 13 Twp. 33 Rge. 30 ~~(E)~~ (W)

County: Meade Total Depth 6294 Oil Well X

Gas Well Input Well GWD Well D & A X Lost Hole

Mr. Burriss was instructed to plug the well as follows:

8 5/8" to 1472' circulated w/ cement. Mud 6294' to 1485'
Spot 30 sacks cement 1485' to 1385' Mud 1385' to 40'
Plug, Hulls & 10 sacks cement 40' to 0'

Very truly yours,

[Signature]
Conservation Division Agent