



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

RECEIVED
STATE CORPORATION COMMISSION
JAN 15 1973
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Hicks of Jet Drlg. has this

date requested permission to plug the following described well:

Mr. Hicks guarantees payment of the plugging fee.

Operator's full Name: Jet Drlg. Co. & Zetco Petro.

Complete Address: 514 One Twenty Bldg., Wichita, Ks.

Lease Name: Sisters of St. Agnes Well No. 3

Location: NE SE NW Sec. 20 Twp. 11 Rge. (E)(W) 16

County: Ellis Total Depth 3356' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Hicks was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 500' and displace
50 sk cmt thru drill pipe. Heavy mud to 240' set cementing plug and
displace 25 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug,
1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo Z. Masarik
Conservation Division Agent