

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION OCT 1 1973 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 800 XXXXXXXX XXXXXXXX Wichita, Kansas 67202

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Glenn N. Rupe guarantees payment of the plugging fee.

Operator's full Name: Glenn N. Rupe

Complete Address: 920 O. W. Garvey Bldg., Wichita, Kansas

Lease Name: Potter "B" Well No. # 1

Location: SW NW NE Sec. 20 Twp. 11 Rge. 16 (E)(W) W

County: Ellis Total Depth 3325 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Tom Buffington was instructed to plug the well as follows:

8 5/8" csg. 650' Cwc.

Circulated hole with heavy mud to 650', set plug, & displaced 50 sax cement thru drill pipe. Mud to 300' & displaced 25 sax cement thru

drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax

cement with Sun Cementing Company's pump truck, cementing to base

of cellar.

Very truly yours,

Don Luman Conservation Division Agent