

CONFIDENTIAL

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

ORIGINAL

Form ACO-1
September 1999
Form Must Be Typed

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

7/28/08

Operator: License # 33476
Name: FIML Natural Resources, LLC
Address: 410 17th Street Ste. 900
City/State/Zip: Denver, CO. 80202
Purchaser: NCRA
Operator Contact Person: Cassandra Parks
Phone: (303) 893-5090
Contractor: Name: Murfin Drilling Company
License: 30606

Wellsite Geologist: _____
Designate Type of Completion:
 New Well Re-Entry Workover
 Oil SWD SLOW Temp. Abd.
 Gas ENHR SIGW
 Dry Other (Core, WSW, Expl., Cathodic, etc)

If Workover/Re-entry: Old Well Info as follows:
Operator: KCC

Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to Enhr./SWD
 Plug Back _____ Plug Back Total Depth _____
 Commingled _____ Docket No. _____
 Dual Completion _____ Docket No. _____
 Other (SWD or Enhr.?) _____ Docket No. _____

4/30/2008 5/10/2008 6/16/2008
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 171-20688-0000
County: Scott
S2 S2 NW SW Sec. 32 Twp. 18 S. R. 31 East West
1,450 feet from S / N (circle one) Line of Section
660 feet from E / W (circle one) Line of Section

Footages Calculated from Nearest Outside Section Corner:
(circle one) NE SE NW SW

Lease Name: Christy Well #: 12-32-1831
Field Name: Unknown

Producing Formation: Lansing
Elevation: Ground: 2974' Kelly Bushing: 2984'

Total Depth: 4751 Plug Back Total Depth: _____
Amount of Surface Pipe Set and Cemented at 9 jts @ 403 Feet
Multiple Stage Cementing Collar Used? Yes No

If yes, show depth set 2983 (DV tool) Feet
If Alternate II completion, cement circulated from 2983
feet depth to surface w/ 590 sx cmt.

Drilling Fluid Management Plan AM II NH 10-1408
(Data must be collected from the Reserve Pit)


Chloride content 3800 ppm Fluid volume 500 bbls
Dewatering method used Evaporation/backfill

Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License No.: _____
Quarter _____ Sec. _____ Twp. _____ S. R. _____ East West
County: _____ Docket No.: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

All requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.

Signature: [Signature]
Title: Regulatory Specialist Date: 7/28/2008
Subscribed and sworn to before me this 28th day of July
2008
Notary Public: Linda S. Busk
Date Commission Expires: My Commission Expires 09/01/2009



KCC Office Use ONLY

Letter of Confidentiality Received
If Denied, Yes Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 30 2008

CONFIDENTIAL

Side Two

Operator Name: FIML Natural Resources, LLC Lease Name: Christy Well #: 12-37-1831
Sec. 32 Twp. 18 S. R. 31 East West County: Scott

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <i>(Attach Additional Sheets)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	<input checked="" type="checkbox"/> Log	Formation (Top), Depth and Datum	<input type="checkbox"/> Sample
Samples Sent to Geological Survey	<input type="checkbox"/> Yes <input type="checkbox"/> No	Name	Top	Datum
Cores Taken	<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	Topeka	3668'	-684
Electric Log Run <i>(Submit Copy)</i>	<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	Heebner	3905'	-921
List All E. Logs Run:		Lansing	3943'	-959
		Kansas City	4319'	-1335
		Marmaton	4352'	-1368

Triple Combo; Microlog

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12-1/4"	8-5/8"	24.0	403'	Class "A"	255	2% gel & 3% CaCl2
Production	7-7/8"	5-1/2"	15.5	4742'	ASC	345	2% gel & 10% salt
				2983' (DV tool)	Lightweight	590	0.25 pps flo & 5.0 gil

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				


Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record (Amount and Kind of Material Used)	Depth
1	4401-4406' CIBP @ 4390'	Acidize w/ 1218 gal 15% MCA & 2000 gal 15% N-E	4401-06'
1	4309-4312'	Acidize w/ 672 gal 15% MCA acid	4309-12'
1	4225-4228'	Acidize w/ 672 gal 15% MCA acid	4225-28'

TUBING RECORD	Size 2-7/8"	Set At 4352'	Packer At	Liner Run <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No
---------------	----------------	-----------------	-----------	--

Date of First, Resumerd Production, SWD or Enhr. 6/25/2008	Producing Method <input type="checkbox"/> Flowing <input checked="" type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other (Explain)
Estimated Production Per 24 Hours Oil Bbls. 153	Gas MA Water Bbls. 98
Gas-Oil Ratio	Gravity

Disposition of Gas: Vented Sold Used on Lease *(If vented, Submit ACO-18.)*

METHOD OF COMPLETION: Open Hole Perf. Usually Comp. Commingled



ALLIED

CEMENTING CO., LLC
Cementing & Acidizing Services

24 S. Lincoln Street
P.O. Box 31
Russell, KS 67665-2906

Voice: (785) 483-3887
Fax: (785) 483-5566

INVOICE

Invoice Number: 113938
Invoice Date: May 13, 2008
Page: 1

2347

Bill To:

FIML Natural Resources
LLC
410 17th St., #900
Denver, CO 80202

Customer ID	Well Name/# or Customer P.O.	Payment Terms	
FIML	Christy #12-32-1831	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS	Oakley	May 13, 2008	6/12/08

Quantity	Item	Description	Unit Price	Amount
590.00	MAT	Lightweight Class A	12.65	7,463.50
2,950.00	MAT	Gilsonite	0.80	2,360.00
148.00	MAT	Flo Seal	2.25	333.00
705.00	SER	Handling	2.15	1,515.75
55.00	SER	Mileage 705 sx @.09 per sk per mi	63.45	3,489.75
1.00	SER	Production String - Top Stage	1,075.00	1,075.00

CONFIDENTIAL
JUL 28 2008
KCC

8270-118
Adam D. Blue
" 2nd Stage "

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2008
CONSERVATION DIVISION
WICHITA, KS

ALL PRICES ARE NET, PAYABLE
30 DAYS FOLLOWING DATE OF
INVOICE. 1 1/2% CHARGED
THEREAFTER. IF ACCOUNT IS
CURRENT, TAKE DISCOUNT OF

\$ 1623.70

ONLY IF PAID ON OR BEFORE

Jun 12, 2008

Subtotal	16,237.00
Sales Tax	639.86
Total Invoice Amount	16,876.86
Payment/Credit Applied	
TOTAL	16,876.86

D08006

1623.70
15253.16

ALLIED CEMENTING CO., LLC. 31968

REMIT TO: P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:
Oakley, KS

DATE <u>5-11-08</u>	SEC. <u>12</u>	TWP. <u>32</u>	RANGE <u>31</u>	CALLED OUT	ON LOCATION <u>10:00am</u>	JOB START <u>11:30pm</u>	JOB FINISH <u>12:45am</u>
LEASE <u>Christy</u>		WELL # <u>12-32-1831</u>		LOCATION <u>Scott City 66-45-1E</u>		COUNTY <u>Scott</u>	STATE <u>KS</u>
OLD OR <u>NEW</u> (Circle one)				<u>NO</u>			

CONTRACTOR Murphy #14

TYPE OF JOB 2-stage (Top)

HOLE SIZE 7 7/8 T.D. 4750

CASING SIZE 5"2 DEPTH 2982'

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT _____

PERFS. _____

DISPLACEMENT 70.9 BBHs

OWNER same

CEMENT

AMOUNT ORDERED 590 Lide

5# 5.1/SK 114# Flo-seal

RECEIVED			
KANSAS CORPORATION COMMISSION			
COMMON _____	@ _____	JUL 25 2008	
POZMIX _____	@ _____		
GEL _____	@ _____	CONSERVATION DIVISION	
CHLORIDE _____	@ _____	WICHITA, KS	
ASC _____	@ _____		
Lide <u>590</u>	@ <u>12</u>	<u>7463</u>	<u>50</u>
Gilsonite <u>2950#</u>	@ <u>.80</u>	<u>2360</u>	<u>00</u>
Flo-seal <u>148#</u>	@ <u>2.25</u>	<u>333</u>	<u>00</u>
HANDLING <u>705</u>	@ <u>2.15</u>	<u>1515</u>	<u>75</u>
MILEAGE <u>.0955 km</u>		<u>3489</u>	<u>75</u>
		TOTAL	<u>15162</u>

EQUIPMENT

PUMP TRUCK CEMENTER Ruzzo

431 HELPER Kelly

BULK TRUCK

377 DRIVER LaBene

BULK TRUCK

394 DRIVER _____

REMARKS:

mix 10 gals MH, 15 gals in RLH

mix 565 gals Lide 5# 5.1/SK 114# Flo-seal

washout pump & lines. Displace

plug to DU Tool. 800# Lide

Close DU Tool @ 1500# Cement

did circulate approx 30 BBHs

Plug down @ 12:45am

Thanks Ruzzo & crew

SERVICE

DEPTH OF JOB 2982'

PUMP TRUCK CHARGE 1075

EXTRA FOOTAGE @ _____

MILEAGE @ NA

MANIFOLD @ _____

TOTAL _____

CHARGE TO: FIMH NAT. RES

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

_____ @ _____

TOTAL _____

To Allied Cementing Co., LLC.

You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Terrance R. Heighter

SIGNATURE Terrance R. Heighter

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS



ALLIED

CEMENTING CO., LLC
Cementing & Acidizing Services

RECEIVED
MAY 07 2008
2347

INVOICE

24 S. Lincoln Street
P.O. Box 31
Russell, KS 67665-2906

Voice: (785) 483-3887
Fax: (785) 483-5566

Invoice Number: 113746

Invoice Date: Apr 30, 2008

Page: 1

Bill To:
FIML Natural Resources LLC 410 17th St., #900 Denver, CO 80202

Customer ID	Well Name/# or Customer P.O.	Payment Terms	
FIML	Christy #12-32-1831	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS	Oakley	Apr 30, 2008	5/30/08

Quantity	Item	Description	Unit Price	Amount
255.00	MAT	Class A Common	14.20	3,621.00
5.00	MAT	Gel	18.75	93.75
9.00	MAT	Chloride	52.45	472.05
269.00	SER	Handling	2.15	578.35
55.00	SER	Mileage 269 sx @.09 per sk per mi	24.21	1,331.55
1.00	SER	Surface	917.00	917.00
103.00	SER	Extra Footage	0.80	82.40
55.00	SER	Mileage Pump Truck	7.00	385.00
1.00	EQP	Guide Shoe	282.00	282.00
1.00	EQP	AFU Insert	377.00	377.00
3.00	EQP	Centralizers	62.00	186.00
1.00	EQP	Rubber Plug	113.00	113.00

CONFIDENTIAL

JUL 28 2008

KCC

8100-145
Adam D. Bl...

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2008
CONSERVATION DIVISION
WICHITA, KS

ALL PRICES ARE NET, PAYABLE
30 DAYS FOLLOWING DATE OF
INVOICE. 1 1/2% CHARGED
THEREAFTER. IF ACCOUNT IS
CURRENT, TAKE DISCOUNT OF

\$ 843.91

ONLY IF PAID ON OR BEFORE

May 30, 2008

Subtotal	8,439.10
Sales Tax	324.12
Total Invoice Amount	8,763.22
Payment/Credit Applied	
TOTAL	8,763.22

D08006

(843.91)
7919.31

ALLIED CEMENTING CO., LLC. 31905

REMIT TO: P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Oakley

DATE <u>4-30-08</u>	SEC. <u>32</u>	TWP. <u>18^s</u>	RANGE <u>31^w</u>	CALLED OUT	ON LOCATION <u>8:30 PM</u>	JOB START <u>4:00 AM</u>	JOB FINISH <u>4:30 AM</u>
LEASE <u>Christy</u>	WELL # <u>12-321831</u>	LOCATION <u>Scott City, 6E-4S-34E</u>	COUNTY <u>Scott</u>	STATE <u>Kan</u>	OLD OR NEW (Circle one) <u>NEW</u>		

CONTRACTOR MurFin Dls Co #14

TYPE OF JOB Surface

HOLE SIZE 7 1/4 T.D. 406'

CASING SIZE 8 5/8 DEPTH 408

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT 43.19'

CEMENT LEFT IN CSO 43.19

PERFS. CONFIDENTIAL

DISPLACEMENT 2008 23 1/4 BBL

OWNER Same

CEMENT

AMOUNT ORDERED 255 sks com

3% CC - 2% Gel

COMMON	<u>255-sks @</u>	<u>14.20</u>	<u>3,621.00</u>
POZMIX	@		
GEL	<u>5 sks @</u>	<u>18.75</u>	<u>93.75</u>
CHLORIDE	<u>9 sks @</u>	<u>52.45</u>	<u>472.05</u>
ASC	@		

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2008
CONSERVATION DIVISION
WICHITA, KS

KCC EQUIPMENT

PUMP TRUCK CEMENTER Walt

423-281 HELPER Alvin

BULK TRUCK

218 DRIVER Larene

BULK TRUCK

DRIVER

HANDLING	<u>269-sks @</u>	<u>2.15</u>	<u>578.35</u>
MILEAGE	<u>9¢ per sk/mile</u>		<u>1,331.55</u>
TOTAL			<u>6,096.70</u>

REMARKS:

Cement Did Cure
approx 6 BBL to Pit

Thank You

CHARGE TO: F I M L

STREET _____

CITY _____ STATE _____ ZIP _____

SERVICE

DEPTH OF JOB			
PUMP TRUCK CHARGE			<u>917.00</u>
EXTRA FOOTAGE <u>108'</u>	@ <u>.80¢</u>		<u>82.40</u>
MILEAGE <u>5.5 miles</u>	@ <u>7.00</u>		<u>385.00</u>
MANIFOLD	@		

TOTAL 1,388.40

PLUG & FLOAT EQUIPMENT

	<u>8 5/8</u>		
1- Guide Shoe	@		<u>282.00</u>
1-AFU insert	@		<u>377.00</u>
3- Centralizers	@ <u>62.00</u>		<u>186.00</u>
1- Rubber Plug	@		<u>113.00</u>

TOTAL 958.00

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME W Gary Duke

SIGNATURE [Signature]

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____

IF PAID IN 30 DAYS

JUL 25 2008

RECEIVED

ALLIED

CEMENTING CO., LLC
Cementing & Acidizing Services

24 S. Lincoln Street
P.O. Box 31
Russell, KS 67665-2906

Voice: (785) 483-3887
Fax: (785) 483-5566

INVOICE

Invoice Number: 113937

Invoice Date: May 13, 2008

Page:

RECEIVED
MAY 16 2008

Bill To:

FIML Natural Resources
LLC
410 I7th St., #900
Denver, CO 80202

2347

Customer ID	Well Name/# or Customer P.O.	Payment Terms	
FIML	Christy #12-32-1831	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS	Oakley	May 13, 2008	6/12/08

Quantity	Item	Description	Unit Price	Amount
6.00	MAT	Gel	18.75	112.50
345.00	MAT	ASC Class A	16.75	5,778.75
36.00	MAT	Salt	21.60	777.60
500.00	MAT	WFR-2	1.15	575.00
426.00	SER	Handling	2.15	915.90
55.00	SER	Mileage 426 sx @.09 per sk per mi	38.34	2,108.70
1.00	SER	Production String - Bottom Stage	1,969.00	1,969.00
55.00	SER	Mileage Pump Truck	7.00	385.00
1.00	SER	Manifold & Head Rental	113.00	113.00
1.00	EQP	Non Fill Float Shoe	529.00	529.00
1.00	EQP	Sure Seal Float Collar	372.00	372.00
1.00	EQP	D V Tool	4,500.00	4,500.00
2.00	EQP	Baskets	186.00	372.00
1.00	EQP	Lock Ring	29.00	29.00
24.00	EQP	Centralizers	57.00	1,368.00

CONFIDENTIAL
MAY 28 2008
KCC

RECEIVED
KANSAS CORPORATION COMMISSION
JUL 25 2008
CONSERVATION DIVISION
WICHITA, KS

8200-118
Adam J. Blue
cc 1st stg

ALL PRICES ARE NET, PAYABLE
30 DAYS FOLLOWING DATE OF
INVOICE. 1 1/2% CHARGED
THEREAFTER. IF ACCOUNT IS
CURRENT, TAKE DISCOUNT OF

\$ 1990.54

ONLY IF PAID ON OR BEFORE

Jun 12, 2008

Subtotal	19,905.45
Sales Tax	908.07
Total Invoice Amount	20,813.52
Payment/Credit Applied	
TOTAL	20,813.52

D08006

1990.54
18,822.98

ALLIED CEMENTING CO., LLC. 31967

REMIT TO: P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Onkley, KS

DATE <u>5-11-08</u>	SEC. <u>12</u>	TWP. <u>32</u>	RANGE <u>1 31</u>	CALLED OUT	ON LOCATION <u>10:00am</u>	JOB START <u>6:30am</u>	JOB FINISH <u>7:30pm</u>
LEASE <u>Chrisdy</u>	WELL # <u>12-32-1831</u>	LOCATION <u>Sron City 6645-16</u>			COUNTY <u>Stott</u>	STATE <u>RECEIVED</u>	
OLD OR <input checked="" type="radio"/> NEW (Circle one)						KANSAS CORPORATION COMMISSION	

JUL 25 2008

CONTRACTOR Mundin #14

TYPE OF JOB 2-stage (Bottom)

HOLE SIZE 7 7/8 T.D. 4750 62

CASING SIZE 5 1/2 15.5 DEPTH 4741

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL DU-Tool DEPTH 2982 00

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT 22 60

CEMENT LEFT IN CSG. 22 60

OWNER Some

CEMENT

AMOUNT ORDERED 345 SKS ASC

290 gal 10% salt

500 gal WFA II

COMMON	@		
POZMIX	@		
GEL	@	<u>6</u>	<u>18 25</u>
CHLORIDE	@		
ASC	@	<u>345</u>	<u>5778 25</u>
Salt	@	<u>365 SKS</u>	<u>21 60</u>
WFA II	@	<u>500</u>	<u>1 15</u>
	@		
	@		
	@		
HANDLING	@	<u>426</u>	<u>2 15</u>
MILEAGE	@	<u>.09 x 94 mile</u>	<u>2108 20</u>
TOTAL			<u>10 268 45</u>

DISPLACEMENT 112.31 BBL

CONFIDENTIAL

JUL 25 2008

PUMP TRUCK # 431 CEMENTER Fuzzy HELPER Kelly

BULK TRUCK # 399 DRIVER Wilbur

BULK TRUCK # _____ DRIVER _____

REMARKS:

Mix 500 gal WFA II, mix 345 SKS ASC 290 gal 10% salt, washout pump lines, Displace plus to float collar, hit press 800# hand press 1500#, float held, Drop DU Bank wait 15 min, Open tool @ 800# Circ 4 hrs, 1st plus down @ 7:15pm Thanks Fuzzy & crew

SERVICE

DEPTH OF JOB		<u>4741 62</u>
PUMP TRUCK CHARGE		<u>1969 00</u>
EXTRA FOOTAGE	@	
MILEAGE	@	<u>55</u> <u>7 00</u> <u>385 00</u>
MANIFOLD + head	@	<u>113 00</u>
	@	
	@	
TOTAL		

CHARGE TO: FIMH Natural Res

STREET _____

CITY _____ STATE _____ ZIP _____

PLUG & FLOAT EQUIPMENT

<u>1- won fill float shoe</u>	@	<u>529 00</u>
<u>1- Sure seal fl. collar</u>	@	<u>372 00</u>
<u>1- DU Tool</u>	@	<u>4500 00</u>
<u>2- Baskets</u>	@	<u>196 00</u> <u>372 00</u>
<u>1- Loc. Pins</u>	@	<u>29 00</u>
<u>24- Centralizers</u>	@	<u>57 00</u> <u>1368 00</u>
TOTAL		

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME Terrence R Lighter

SIGNATURE Terrence R Lighter

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS