

TO:

9-29 3021380

15-001-02534-00-00

API NUMBER 15- CONTROL #980011

STATE CORPORATION COMMISSION

NW, SEC. 10, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

2775
4345 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

4400
4730 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE OLSON-MANION-STOLL WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

101

WELL TOTAL DEPTH 800' FEET

OPERATOR: STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 6 FEET 20

ADDRESS

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD WELL ☐ D/A ☐

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR K.W. OIL WELL SERVICE

LICENSE NUMBER 3097

ADDRESS 19450 FORD ROAD, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 11:30AM DAY: 29 MONTH: 9 YEAR: 97

PLUGGING PROPOSAL RECEIVED FROM JIM KEPLEY

(COMPANY NAME) K.W. OIL WELL SERVICE (PHONE) 316-431-2285

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD APPARENTLY BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2" FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☒ PART ☐ NONE ☐

OPERATIONS COMPLETED: HOUR: 12:30 PM DAY: 29 MONTH: 9 YEAR: 97

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 2" CASING TO 775'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 1" AND 2" ANNULUS AT SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGES AND DISPLACEMENT WERE FILLED FROM SURFACE. 35 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3