

TO:

10-3

3021378

15-001-02536-00-00

API NUMBER 15- CONTROL #980011

STATE CORPORATION COMMISSION

NW, SEC. 10, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

3935 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

4070 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE OLSON-MANION-STOLL WELL # 3

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

101

WELL TOTAL DEPTH 800' FEET

OPERATOR: STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 8 FEET 20

ADDRESS

ABANDONED OIL WELL GAS WELL INPUT WELL X SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR K.W. OIL WELL SERVICE

LICENSE NUMBER

RECEIVED
AS
OCT 28
D 12:12

3097

ADDRESS 19450 FORD ROAD, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 1:00 PM DAY: 3 MONTH: 10

YEAR: 97

PLUGGING PROPOSAL RECEIVED FROM JIM KEPLEY

(COMPANY NAME) K.W. OIL WELL SERVICE

(PHONE) 316-431-2285

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN AT TD ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 3 MONTH: 10 YEAR: 97

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE 2" CASING TO 700'. 1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 500'. CEMENT WAS PUMPED INTO THE 1" PIPE INSIDE THE 2" UNTIL CEMENT CIRCULATED FROM THE 1" AND 2" ANNULUS AT SURFACE. CEMENT WAS PUMPED INTO THE 1" PIPE IN THE 2" AND 8" ANNULUS UNTIL CEMENT CIRCULATED FROM THE 8" AT SURFACE. ALL 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. 185 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3