

3021395

TO:

10-21

API NUMBER 15- 15-001-02548-00-00
CONTROL #980011

STATE CORPORATION COMMISSION

NW, SEC. 10, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

4785 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

4510 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE OLSON-MANION-STOLL WELL # E

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE #

101

WELL TOTAL DEPTH 800' FEET

OPERATOR: STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 8 FEET 20

ADDRESS

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD WELL ☐ D/A ☐

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR K.W. OIL WELL SERVICE

LICENSE NUMBER 93097

ADDRESS 19450 FORD ROAD, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 21 MONTH: 10 YEAR: 97

PLUGGING PROPOSAL RECEIVED FROM JIM KEPLEY

(COMPANY NAME) K.W. OIL WELL SERVICE (PHONE) 316-431-2285

WERE: VISIBLE AT SURFACE ON THIS WELL WAS 8" SURFACE CASING THAT WAS FULL OF DIRT.

THE PLUGGING PROPOSAL WAS TO WASH 1" PIPE TO AS DEEP A DEPTH AS POSSIBLE AND CIRCULATE CEMENT TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☒ PART ☐ NONE ☐

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 21 MONTH: 10 YEAR: 97

ACTUAL PLUGGING REPORT 1" PIPE WAS WASHED INTO THE WELL TO 600'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 8" SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. 196 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3