

3021397

TO:

10-21

API NUMBER 15- CONTROL #980011

STATE CORPORATION COMMISSION

NW, SEC. 10, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION 3190 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3385 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE OLSON-MANION-STOLL WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE # 101

WELL TOTAL DEPTH 800' FEET

OPERATOR: STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 7 FEET 20

ADDRESS

ABANDONED OIL WELL ☒ GAS WELL ☐ INPUT WELL ☐ SWD WELL ☐ D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR K.W. OIL WELL SERVICE LICENSE NUMBER 3097

ADDRESS 19450 FORD ROAD, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 11:00 AM DAY: 21 MONTH: 10 YEAR: 97

PLUGGING PROPOSAL RECEIVED FROM JIM KEPLEY

(COMPANY NAME) K.W. OIL WELL SERVICE (PHONE) 316-431-2285

WERE: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 800' THAT HAD APPARENTLY
BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2" CASING
FULL OF CEMENT FROM SURFACE.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL ☒ PART ☐ NONE ☐

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 21 MONTH: 10 YEAR: 97

ACTUAL PLUGGING REPORT THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2" CASING.


COTTONSEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS
PUMPED INTO THE 2" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT-IN
AT 600 PSI. 28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY CONSOLIDATED INDUSTRIAL
SERVICES, INC.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED


(TECHNICIAN)

FORM CP-2/3