

3021398

TO:

10-27

API NUMBER 15- CONTROL #980011

15-001-02554-00-00

STATE CORPORATION COMMISSION

NW, SEC. 10, T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

4730 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

4740 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE OLSON-MANION-STOLL WELL # K

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLENOPERATOR LICENSE # 101WELL TOTAL DEPTH 800' FEETOPERATOR: STATE OF KANSASCONDUCTOR PIPE: SIZE FEET NAME AND FEE FUND PLUGGINGSURFACE CASING: SIZE 8 FEET 20ADDRESS ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A OTHER WELL AS HEREINAFTER INDICATED PLUGGING CONTRACTOR K.W. OIL WELL SERVICE LICENSE NUMBER 3097ADDRESS 19450 FORD ROAD, CHANUTE, KS 66720COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 27 MONTH: 10 YEAR: 97PLUGGING PROPOSAL RECEIVED FROM JIM KEPLEY(COMPANY NAME) K.W. OIL WELL SERVICE (PHONE) 316-431-2285WERE: VISIBLE AT SURFACE ON THIS WELL WAS 8" SURFACE CASING FULL OF DIRT AND ROCK.THE PLUGGING PROPOSAL WAS TO DRILL TO AS DEEP A DEPTH AS POSSIBLE INTO THE WELL AND
CIRCULATE CEMENT TO SURFACE.PLUGGING PROPOSAL RECEIVED BY C.P. TITELPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 27 MONTH: 10 YEAR: 97

ACTUAL PLUGGING REPORT THE WELL WAS DRILLED OUT TO 475'. 1" PIPE WAS RAN INTO THE
8" SURFACE CASING TO 475'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED
FROM THE 1" AND 8" ANNULUS AT SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGE AND
DISPLACEMENT WERE FILLED FROM SURFACE. 231 SACKS OF CEMENT WERE PUMPED INTO THIS
WELL BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

REMARKS: (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3