

TO:

- 10-3 3021376

15-001-02555-00-00
API NUMBER 15- CONTROL #980011

STATE CORPORATION COMMISSION

NW , SEC. 10 , T 26 S, R 18 E

CONSERVATION DIVISION - PLUGGING SECTION

3660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET

3905 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE OLSON-MANION-STOLL WELL # W.W.

TECHNICIAN'S PLUGGING REPORT

COUNTY ALLEN

OPERATOR LICENSE # 101

WELL TOTAL DEPTH 300' FEET

OPERATOR: KOC STATE OF KANSAS

CONDUCTOR PIPE: SIZE FEET

NAME AND FEE FUND PLUGGING

SURFACE CASING: SIZE 7 FEET 20

ADDRESS

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR K.W. OIL WELL SERVICE LICENSE NUMBER 3097

ADDRESS 19450 FORD ROAD, CHANUTE, KS 66720

COMPANY TO PLUG AT: HOUR: 10:00AM DAY: 3 MONTH: 10 YEAR: 97

PLUGGING PROPOSAL RECEIVED FROM JIM KEPLEY

(COMPANY NAME) K.W. OIL WELL SERVICE (PHONE) 316-431-2285

WERE: THIS WELL PROBABLY CONSISTED OF AN UNCAPPED 6" BORE TO 300'. EVIDENTLY IT HAD BEEN UTILIZED AS A WATER SUPPLY WELL. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE WELL FULL OF CEMENT.

PLUGGING PROPOSAL RECEIVED BY C.P. TITEL

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:00AM DAY: 3 MONTH: 10 YEAR: 97

ACTUAL PLUGGING REPORT 1" PIPE WAS RAN INTO THE WELL TO 300'. A SOLID OBSTRUCTION WAS ENCOUNTERED AT THAT POINT. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. SETTLAGE AND DISPLACEMENT WERE FILLED FROM SURFACE. 75 SACKS OF CEMENT WERE PUMPED INTO THIS WELL BY CONSOLIDATED INDUSTRIAL SERVICES, INC.

REMARKS:

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID/XXXXXXX) OBSERVE THIS PLUGGING.

SIGNED

Clayton P. Titel
(TECHNICIAN)

FORM CP-2/3