

11-30

1 120171

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,491 - 01-00

See Note, SEC. 33, T 21 S, R 11 W/E

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9069

Lease Name Whooping Crane Well # 2-A

Operator: General Oil Company, Inc.

County Stafford 124.48

Name & Address 1540 North Broadway, Suite 202

Well Total Depth 3830 feet

Wichita, KS 67214

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 253

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SMD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Great Bend Casing Pullers License Number 4635

Address P.O. Box 768, Great Bend, KS 67530

Company to plug at: Hour: 9 a.m. Day: 30 Month: 11 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers (phone) 316-793-9711

were: 5 1/2" at 3830' cemented w/150 sx cement Perfs at 3556-3738' (5 sets)

1st plug sand back to 3500' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

DEC 9 1988

Plugging Proposal received by Steve Durrant (TECHNICIAN)  
Wichita, Kansas

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10 a.m. Day: 30 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 3500' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 90 sx cement.

Pumping pressure 0-900 psi and shut in 900 psi.

NOTE: Directional hole top at C NW SE, Bottom @ C NW SW

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 1460' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(did not observe this plugging.)

DATE 12-12-88

Signed Dean Rankin  
(TECHNICIAN)

INV. NO. 23308