

15185 - 21399-0000 21399 - 0000

To: **1 121074**  
**STATE CORPORATION COMMISSION**  
Wichita State Office Bldg. **PLUGGING SECTION**  
130 S. Market, Room 2078  
Wichita, KS 67202

10-16

API NUMBER **15-** 185-23,399  
C NW SE, SEC. **33**, T **21** S, R **11** W/EK  
1980 feet from S section line  
1980 feet from E section line

**TECHNICIAN'S PLUGGING REPORT**

Operator License # 9069  
Operator: General Oil Co., Inc.  
Name & Address: 1540 N. Broadway  
Wichita, KS 67214

Lease Name Whooping Crane Well # 1  
County Stafford  
Well Total Depth 3500 <sup>112.75</sup> feet  
Conductor Pipe: Size 13 1/2 feet 80  
Surface Casing: Size 8 5/8 feet 232

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 5:30 p.m. Day: 16 Month: 10 Year: 1995

Plugging proposal received from Darrell Kelso

(company name) Mike's Testing & Salvage Inc. (phone) 316-938-2943

were: 5 1/2" at 3499' w/175 sx cement, PBDT 3450', Perfs at 3412-18'

1st plug set CIBP at 3370' with 2 sx cement on top,

2nd plug perforate 5 1/2" casing at 550' and circulate cement.

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 7:30 p.m. Day: 16 Month: 10 Year: 1995

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3370' and dumped 2 sx cement on top,

2nd plug perforated 5 1/2" casing at 550' and circulated cement with 160 <sup>RECEIVED</sup> ~~160~~ <sup>5</sup> sx

gel.

STATE CORPORATION COMMISSION

OCT 23 1995

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
I (did / did not) observe this plugging.

DATE 10-27-95

Signed Steve Middleton  
(TECHNICIAN)

INV. NO. 43867