

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20598-00-01
Spot: SWNW Sec/Twnshp/Rge: 4-34S-41W
1980 feet from N Section Line, 660 feet from W Section Line
Lease/Unit Name: CHEROKEE Well Number: D-1
County: MORTON Total Vertical Depth: 5136 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: 1201 LAKE ROBBINS DRIVE
THE WOODLANDS, TX 77380

Production Casing Size: 5.5 feet: 5163 WITH 150 SX CMT
Surface Casing Size: 8.625 feet: 1409 WITH 500 SX CMT

#76692

Well Type: OIL UIC Docket No: Date/Time to Plug: 09/02/2003 3:30 PM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGI Phone: (580) 854-6515

Proposed Plugging Method: CIBP @4450' WITH 2 SX CMT. PLUG AT 1410' WITH 50 SX CMT. PLUG AT 660' WITH 30 SX CMT. PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/02/2003 3:30 PM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


PBTD 5157'. PERFS AT 5130-38'. CIBP @ 5100'. PERFS AT 4492-4522'. DV TOOL @ 3317' WITH 125 SX CMT. TOC @ 2200'. CIBP SET AT 4450' WITH 2 SX CMT SPOTTED ON TOP BY DUMP BAILER. 1ST PLUG PULLED UP TO 1430'. LOADED HOLE WITH MUD AND PUMPED 50 SX CMT. GOOD CIRCULATION THROUGHOUT. 2ND PLUG PULLED CASING TO 660' & PUMPED 30 SX CMT. 3RD PLUG PULLED CASING TO 40-0' & PUMPED 10 SX CMT.

RECEIVED
SEP 19 2003
KCC WICHITA

Remarks: USED COMMON CMT BY SARGENTS. RECOVERED 1520' OF 5 1/2" CASING.

Plugged through: CSG

District: 01



Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED

DATE 9-19-03

INV. NO. 2004060524

F60 CP-2/3