

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

4-7 15-191-1003-00-02 2-040803
~~15-191-000~~

API NUMBER: D-22,376

SW SW NE, SECTION 28 TOWNSHIP 31 RANGE 1W

OPERATOR LICENSE # 9809

2970 FEET FROM S SECTION LINE
2310 FEET FROM E SECTION LINE

OPERATOR MERIDETH ENTERPRISES INC
NAME & RR 1
ADDRESS WELLINGTON KS 67152

LEASE NAME: MERIDETH #1

COUNTY: SUMNER

WELL TOTAL DEPTH: 2981' 96.88

PIPE: 4-1/2" @ 2854'

SURFACE CASING: 10-1/4" @ 320'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SLD X D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: COOPER OIL
ADDRESS: 520 N PARALLEL DR., ANDOVER KS LICENSE: 6154

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: HOMER COOPER
COMPANY NAME: COOPER OIL PHONE: 316-

WERE: PERFS 2675'-88' - SAND TO 2625' & 4 SX - CIRC CMT
FROM 450' TO 0'

PLUGGING PROPOSAL RECEIVED BY: DISTRICT 2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 13:30 DAY: 7 MONTH: 4 YEAR: 1995

ACTUAL PLUGGING REPORT:

PERFS WERE COVERED W/SAND FROM 2800' TO 2625' &
CAPPED W/4 SX CMT - 4-1/2" CSG WAS RECOVERED FROM 671'
& PULLED FROM WELLBORE - 2-3/8" TUBING WAS RUN TO 450'
& CMT WAS CIRC TO SURF

REMARKS: SUN CEMENTING 60/40 4% GEL

I DID OBSERVE THIS PLUGGING.

INVOICED
DATE 4-27-95
INV. NO. 42707

Steve Van Gieson
Steve Van Gieson (AGENT)

RECEIVED
KANSAS CORPORATION COMMISSION
APR 25 1995
FORM CP-2/3
REV. 3/90
CONSERVATION DIVISION
WICHITA, KS