

1031548

TO  
STATE CORPORATION COMMISSIONAPI NUMBER 15-081-10,005-0001  
C NW NE SEC. 12, T 30 S, R 34 WCONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINEWICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME DUDLEY TOWNSHIP WELL # 2

TECHNICIAN'S PLUGGING REPORT

COUNTY HASKELLOPERATOR LICENSE # 4824WELL TOTAL DEPTH 4854 FEETOPERATOR: PIONEER NATURAL RESOURCES PRODUCTION CSG: SIZE 5½" @ 4848' WITH 275 SXNAME AND 5205 N O'CONNOR BLVD, SUITE 1400 SURFACE CASING: SIZE 8½" @ 765' WITH 575 SXADDRESS IRVING, TX 75039ABANDONED OIL WELL        GAS WELL        INPUT WELL        SWD WELL D-12,278 / D/AOTHER WELL AS HEREINAFTER INDICATED       PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. LICENSE NUMBER 31151ADDRESS RR 1, BOX 49BA TYRONE, OK 73951COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 05 MONTH: 05 YEAR: 2000PLUGGING PROPOSAL RECEIVED FROM DON HORTON(COMPANY NAME) SARGENT & HORTON PLUGGING, INC. (PHONE) 405-854-6515WERE: PERFS AT 3736-3753. CIBP @ 3840'.SET CIBP AT 3673 WITH 10 SX CEMENT. 1ST PLUG AT 741' WITH 50 SX CEMENT AND MUD.2ND PLUG AT 345' WITH 30 SX CEMENT. 3RD PLUG AT 0-40' WITH 10 SX CEMENT.PLUGGING PROPOSAL RECEIVED BY STEVE DURRANTPLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART        NONE       OPERATIONS COMPLETED: HOUR: 11:45 AM DAY: 05 MONTH: 05 YEAR: 2000ACTUAL PLUGGING REPORT       SET CIBP AT 3673' WITH 10 SX CEMENT. 1ST PLUG AT 741' WITH 50 SX CEMENT AND MUD.2ND PLUG AT 345' WITH 30 SX CEMENT. 3RD PLUG AT 0-40' WITH 10 SX CEMENT.**RECEIVED**  
STATE CORPORATION COMMISSION

MAY 15 2000

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 774' OF 5½" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

CONSERVATION DIVISION  
Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING.

DATE

5/18/00

SIGNED

(TECHNICIAN)

FORM CP-2/3

FILE NO.

61749