

6- 100506

11-26

TO:

API number: 15-051-24,905-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW NW SE /4 SEC. 21, 11 S, 16 W
1650 feet from S section line
2310 feet from E section line

Operator license# 31747

Lease Chrisler well # 1

Operator: Wanita M. Brooks

County Ellis 110.50

Address: 2449 S.W. 90th
Oklahoma City, Ok. 73159

Well total depth 3400 feet
Conductor Pipe: ___ inch @ ___ feet
Surface pipe 8 5/8 Inch @ 658 feet

Aband. oil well ___ , Gas well ___ , Input well ___ , SWD ___ , D & A X

Plugging contractor: Duke Drilling License# 5929

Address: _____

Company to plug at: Hour: ?? Day: _____ Month: _____ Year: _____

Plugging proposal received from: Harvey Moore

Company: Duke Drilling phone: _____

Were: **Spot plugs through drill pipe w/ heavy mud between all plugs.**

1st plug @ 3358 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 970 feet " 25 " Mousehole: ___ sacks

3rd plug @ 700 feet " 40 "

4th plug @ 500 feet " 70 "

5th plug @ 40 feet " **wiper plug & 10sx**

Plugging Proposal Received by: David K. Wann

Plugging operations attended by agent? All[], Part[], None[X]


Completed: Hour: 11:00 pm, Day: 26, Month: November, Year: 1995

Actual plugging report: Hole reported plugged as above.

Order 195 sx 60/40 pozmix w/ 6% gel.

Remarks: Elevation: 1804 GL, Anhydrite depth: 969 - 1007 feet Anhy. plug: YES
Dakota plug: YES Bottom hole plug in place: YES
Plugged through drill pipe: YES
Did penetrate Arbuckle, cemented by Allied Cementing

I did [] / did not [X] observe the plugging.


David K. Wann P.I.R.T. II
(agent)

STATE CORPORATION COMMISSION
RECEIVED
NOV 29 1995
WICHITA, KANSAS

INVOICED
DATE NOV 30 1995

INV. NO. 44156
11-26 FEB 29 1996