

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-22275-00-00

Spot: E2SWSWSW

Sec/Twnshp/Rge: 24-11S-16W

~~330~~ ~~000~~ feet from S Section Line, ~~000~~ <sup>445</sup> feet from W Section Line

Lease/Unit Name: BOWLBY

RT KCC

Well Number: 3

County: ELLIS

Total Vertical Depth: 810 feet

Operator License No.: 6790

Conductor Pipe: Size

feet:

Op Name: CB/JP OIL OPERATIONS

Surface Casing: Size 8.625

feet: 193

w/150 sxs cmt

Address: PO BOX 531

Production: Size 4.5

feet: 786

w/200 sxs cmt

RUSSELL, KS 67665

Liner: Size

feet:

Well Type: SWD

UIC Docket No: D23728.0

Date/Time to Plug: 03/13/2001 9:00 AM

Plug Co. License No.: 6790

Plug Co. Name: CB/JP OIL OPERATIONS

Proposal Rcvd. from: BILL CLAIR

Company: CB/JP OIL OPERATIONS

Phone: (785) 483-6220

Proposed 4 1/2" set at 786' w/200 sxs.

Plugging Pump cement down 4 1/2" casing to pressure.

Method: Ordered out 75 sxs 60/40 pozmix - 10% gel - 500# hulls.

\$35.00

Plugging Proposal Received By: RICHARD WILLIAMS

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 03/13/2001 11:00 AM

KCC Agent: RICHARD WILLIAMS

**Actual Plugging Report:**

Allied pumped 10 sxs 60/40 pozmix - 10% gel down backside.

Max. P.S.I. 500#. S.I.P. 500#. Released.

Pumped 65 sxs 60/40 pozmix - 10% gel with 300# hulls. No pressure.

Shut in 15 minutes. Checked cement 80' from surface.

March 19, 2001 - Cement 80' from surface. Topped off with sand and one sack cement.

**INVOICED**

DATE 3-30-01

2001061550

RECEIVED  
STATE CORPORATION COMMISSION

MAR 27 2001

Remarks: ALLIED CEMENT COMPANY.

Plugged through: CSG

CONSERVATION DIVISION  
Wichita, Kansas

District: 04

Signed

Richard Williams

(TECHNICIAN)

