

6 070681

5-10-88

15-051-05492-00-00

427

R

API NUMBER 15- ~~051-79-028~~ 05492

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

S/2 NE NE, SEC. 30, T 13 S, R 16 (W)E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5816

_____ feet from S section line

_____ feet from E section line

Operator: Chevron U.S.A.

Lease Name Theo Gore Well # 1

Name & Address Box 12116

County Ellis 113.26

Address Oklahoma City, Ok.

Well Total Depth 3485 feet

73157

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 1116

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ U&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Cement Co. & Hembree License Number _____

Address Hays, Ks. and Ellis, Ks.

Company to plug at: Hour: 8:00 AM Day: 10 Month: May Year: 19 88

Plugging proposal received from Mike Russell

(company name) Chevron U.S.A. (phone) _____

were: 8 5/8" 1116' s.p. cwc w/425 sks cement. 5 1/2" casing set at 3476' w/100 sks cement.

P.B.T.D. 3485'. Packer at 3217'. Tubing fish at 3100'. Proposal. Spot cement

through tubing, load and squeeze hole with cement. Shut in under pressure.

Order 75 sks Class A Cement and 200 sks 65/35 Poz 10% Gel.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:45PM Day: 10 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Ordered 75 sks Common Class A Cement and 200 sks Econolite

65/35 Poz 6% Gel spotted through tubing. 1. Ran 2 3/8" tubing to 3070' and

spotted 75 sks Class A Cement. 2. Dia-log tagged cement at 2639' and perforated

casing at 1174'. Halliburton set cement retainer at 1070'. 3. Pumped through

cement retainer 90 sks cement, annulus circulated cement. 4. Stung out of C.R.

and loaded casing with 51 sks cement. Then squeezed casing with 5 sks cement.

Remarks: Max pressure 300 Psig. Shut in a/c. By Halliburton Cement. (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-21-88

INV. NO. 20898

RECEIVED

STATE CORPORATION COMMISSION

CONSERVATION DIVISION

Wichita, Kansas

JUN 6 1988

06-06-88

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt

1