

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 893 21,001

NW, Sec. 13, T 21 S, R 25 W/E

1980' feet from N/S section line

810' feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5816

Lease Name Miner "A" Well # 4-13

Operator: Gulf Oil Co.
Name &
Address Box 2093
Wichita, Ka. 67201

County Hodgeman

Well Total Depth 4600 feet #149.50

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 732

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Barlow well Service License Number 6690

Address West Bend, Mo. 67530

Company to plug at: Hour: NA Day: _____ Month: _____ Year: 19

VERBAL PLUGGING ORDERS GIVEN TO Paul York

(company name) Gulf Oil (phone) 316-653-2576

were: 5 1/2" @ 4590' (Top of Cement 4100) pump 5 barrels mud & 50sx cement on bottom.

Spot plug @ 1550 w/ 50sx cement -> fill hole w/ mud to 767' -> spot 50sx cement - fill hole w/ mud to surface. Push plug to 20' -> fill cement to surface.

Signed Steve Dumont
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None

Operations Completed: Hour: 1:00 PM Day: 21 Month: 4 Year: 1983

ACTUAL PLUGGING REPORT

plugged as ordered.

RCUP
KCC

05-04-83

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Steve Dumont
(TECHNICIAN)

INVOICED

DATE 5-4-83

INV. NO. 4153-W