

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-051-22, 283-0006 R

SE, Sec. 26, T 11 S, R 16 W/E

330 feet from N(S) section line

2310 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6790

Lease Name Shaw Well # C-1

Operator: CB/JB Oil Operations
Name &
Address Natoma, Ks. 67651

County Ellis

Well Total Depth 3353 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Crawford Well Service License Number 6791

Address R.R. #1, Natoma, Ks. 67651

Company to plug at: Hour: 9:30 AM Day: 13 Month: 10 Year: 19 82

VERBAL PLUGGING ORDERS GIVEN TO Bill Clair

(company name) Crawford Well Service (phone) 913-885-4808

were: Order out 25 sacks ⁵⁰ 50 permix-4% gel.-3% ldl. & spot on bottom w/2" tubing. Ordered 165 sacks ⁵⁰ 50 permix-4% gel.-3% ldl., 5 sacks bulls, 20 sacks gel. & 8 5/8" plug.

Signed Ed J. Schel
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:15 PM Day: 13 Month: 10 Year: 19 82

ACTUAL PLUGGING REPORT 8 5/8" 210' S.P. conc. w/125 sacks common, 4 1/2" set at 3352' w/175 sacks common. Top perf. at 3023'. Plugged bottom w/25 sacks ⁵⁰ 50 permix-4% gel.-3% ldl. spotted w/2" tubing. Shot pipe 2 times & recovered 2600'. Ordered 165 sacks ⁵⁰ 50 permix-4% gel.-3% ldl., 5 sacks bulls, 20 sacks gel., & 8 5/8" plug. Pumped in 8 5/8", 25 sacks cement, 4 sacks bulls, 15 sacks gel., 70 sacks cement, 5 sacks gel., 1 sack bulls, rehaired plug & followed w/70 sacks cement

Remarks: Maximum pressure 500 pounds

RECEIVED
STATE CORPORATION COMMISSION

OCT 19 1982

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.
Wichita, Kansas

INVOICED

Signed Ed J. Schel
(TECHNICIAN)

DATE 11-15-82
INV. NO. 1536-U