

7-20

4-060708

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API number: 15-051-22,437-0000

NE NW NW /4 SEC. 26, 11 S, 16 W  
4950 feet from S section line  
4290 feet from E section line

Operator license# 6194

Lease: Bowlby "A" Well # 1

Operator: E.S.P. Development Co., Inc.

County: Ellis 109.85

Address: R.R. #1 - Box 18  
Paradise, Kansas 67658

Well total depth 3380 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 $\frac{1}{2}$  Inch @ 170 feet

Aband. oil well X, Gas well \_\_\_\_\_, Input well \_\_\_\_\_, SWD \_\_\_\_\_, D & A \_\_\_\_\_

Plugging contractor: Co Tools License# \_\_\_\_\_

Address: \_\_\_\_\_

Company to plug at: Hour: 10:00 A.M Day: 20 Month: July Year: 1995

Plugging proposal received from: Charles Farr - Consultant

Company: E.S.P. Development Co., Inc. Phone: 913-998-4413

Were: Order 250 sxs. 60/40 posmix - 10% gel and hulls.  
Plug through Tubing - hole in casing at 516'.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 27 1995

CONSERVATION DIVISION  
WICHITA, KANSAS

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[ X ], Part[ ], None[ ]

Completed: Hour: 2:30 P.M., Day: 20, Month: July, Year: 1995

Actual plugging report: 8 5/8" to 170' with 100 sxs. 4 1/2" to 3378' with 175 sxs. C.I.B.P. at 2610'. Hole in casing at 516'. Perforated at 1550' - 900' - 700'. Ran tubing and tagged plug. Pumped 5 sxs gel followed by 25 sxs cement and displaced to 1600'. Pulled tubing to 1600' and circulated cement to surface with 90 sxs with 300# hulls. Pulled tubing. Tied onto production casing and pumped 120 sxs cement. Max. P.S.I. 300#. S.I.P. 200#. Tied onto annulus. Max. P.S.I. 1500#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD \_\_\_\_\_ Anhy.plug: YES X NO \_\_\_\_\_

Bottom plug(in place): YES X, CALC \_\_\_\_\_, NO \_\_\_\_\_ Dakota plug: YES X, NO \_\_\_\_\_

Plugged through TUBING X, CASING \_\_\_\_\_ Elevation: 1734 GL \_\_\_\_\_

I did X / did not [ ] observe the plugging.

DATE AUG 03 1995

INV. NO. 43235

Herb Deines  
PH (agent)  
Form CP-2/3