

4-060308

4-9  
15-051-02071-0000  
109

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 10-06-63  
W2 SW NW /4 SEC. 20, 11 S, 16 W  
1980 feet from S section line  
4290 feet from E section line

Operator license# 5363 Lease Sisters well # 3

Operator: Berexco, Inc. County Ellis

Address: Box 723 Well total depth 3404 feet  
Hays, Kansas 67601 Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 169 feet

110.63

Aband. oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Berexco, Inc. License# 5363

Address: Box 723, Hays, Kansas 67601

Company to plug at: Hour: 9:00A.M. Day: 9 Month: April Year: 92

Plugging proposal received from: Ted Crawford

Company: Berexco, Inc. Phone: 913-628-6101

Were: Order 300 sks. of 65/35 posmix - 10% gel. - 5 sks. hulls.  
Squeezed at 655' - 720' with 150 sks. on 8-22-78

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[ X ], Part[     ], None[     ]

Completed: Hour: 10:15A.M., Day: 9, Month: April, Year: 92

Actual plugging report: 8 5/8" @ 169' w/150 sks. 5 1/2" @ 3404' w/200  
sk. Top perf. @ 3300'. Pump in 5 1/2" 25 sks. cement followed  
w/5 sks. hulls in 225 sks. cement w/500# hulls. Max. 500#. S.I.P. 500#  
Tied onto annulus and pumped 50 sks. cement. Max. 300#. S.I.P. 200#

RECEIVED  
STATE CORPORATION COMMISSION  
APR 23 1992  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: B.J. Cementing  
Condition of casing(in hole): GOOD X BAD     Anhy.plug: YES X NO      
Bottom plug(in place): YES X, CALC    , NO     Dakota plug: YES X, NO      
Plugged through TUBING    , CASING X. Elevation:     GL    

I  did  did not observe the plugging.

*Herb Deines*

(agent)

Form CP-2/3

INVOICED  
DATE 4-27-92  
INV. NO. 35063

*Jim S.*