

3 023464

15-205-19784-00-00

To:

API NUMBER 20070031-038

STATE CORPORATION COMMISSION

NE,NW,SW 1/4 Sec/Twp/Rge S.3-T.27S.-R.16E.

Wichita State Office Bldg. - PLUGGING SECTION

2072 feet from south section line

130 S. Market, Room 2078

3983 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# WILSON NO.6-I

Operator License # 101

County WILSON

Operator: STATE OF KANSAS

Well Total Depth 950 feet

Name & BUFFALO IV FEE FUND

Production Pipe: 2" Size Feet 950'

Address PLUGGING PROJECT

Surface Casing: 6" Size Feet 40'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: SPLANE PULLING AND ROUSTABOUT SERVICE, INC.

Lic. #

6372
30670

Address: P.O. BOX 386, CAHANUTE KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 14 Month: 1 2009

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 950' THAT HAD

BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE

AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☐ Part ☐

TECHNICIAN

None ☐ X ☒

Operations Completed: Hour: 12:00A.M. Day: 14 Month: 1 2009

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 925'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. 3/4" PIPE WAS WASHED INTO THE 2" AND 6"

ANNULUS TO 375'. CEMENT WAS PUMPED INTO THE 3/4" PIPE UNTIL CEMENT CIRCULATED

FROM THE 6' SURFACE CASING AT SURFACE. THE 3/4" PIPE WAS REMOVED.

DISPLACEMENT WAS FILLED FROM SURFACE. 81 SACKS OF CEMENT WERE PUMPED

INTO THIS WELL.

Remarks: LOCATION ESTABLISHED VIA GPS AS N0.13. THIS WAS NO. 6-I ON THE LEASE MAP.

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:


 TECHNICIAN

 RECEIVED
 KANSAS CORPORATION COMMISSION

JAN 30 2009

 CONSERVATION DIVISION
 WICHITA, KS