

3 023543

15-207-02/61-00-00

To:

API NUMBER

20090015-011

STATE CORPORATION COMMISSION

NW,SW,NE 1/4

Sec/Twp/Rge

S.30-T.26S.-R.17E.

Wichita State Office Bldg. - PLUGGING SECTION

5182 feet from south section line

130 S. Market, Room 2078

1717 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

HEGWALD NO.11

Operator License # 101

County

WOODSON

Operator: STATE OF KANSAS

Well Total Depth 900'

feet

Name & HEGWALD II PLUGGING

Production Pipe:

Size Feet

Address FEE FUNDED PLUGGING

Surface Casing: 8"

Size Feet 40'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, INC.

Lic. #

33749

Address: 19245 FORD RD., CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: 28 Month: 8 2009

Plugging proposal received from: CLAYTON TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 900' THAT HAD BEEN
CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF
THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☐ Part ☐

TECHNICIAN

None

☒

Operations Completed: Hour: 1:00OP.M. Day: 28 Month: 8 2009

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 850'. CEMENT

WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" AT SURFACE.

1" PIPE WAS RAN INTO THE 2" AND 8" ANNULUS TO 540'. CEMENT WAS PUMPED INTO THE 1"

PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS

REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 182 SACKS OF CEMENT WERE

PUMPED INTO THIS WELL.

RECEIVED
KANSAS CORPORATION COMMISSION

NOV 16 2009

Remarks:

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
WICHITA, KS

I DID NOT observe this plugging.

Signed:


TECHNICIAN