

3 023495

15-207-02167-00-00

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 20090015-032  
SE,SE,NW 1/4 Sec/Twp/Rge S.30-T.26S.-R.17E.  
3182 feet from south section line  
2646 feet from east section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 101  
Operator: STATE OF KANSAS FEE FUND  
Name & \_\_\_\_\_  
Address \_\_\_\_\_

Lease/Well# HEGWALD<sup>34</sup> NO.F9G-30  
County ALLEN  
Well Total Depth 900 feet  
Production Pipe: 2" Size Feet 900  
Surface Casing: 8" Size Feet 20'  
AB oil well X Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670  
Address: 19245 FORD ROAD, CHANUTE, KS. 66720

Company to plug at: Hour: 8:00A.M. Day: \_\_\_\_\_ 12 Month: 5 2008

Plugging proposal received from: CLAYTON TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 900' THAT HAD BEEN CEMENTED IN AT AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ Technician X

Operations Completed: Hour: 5:00PM Day: \_\_\_\_\_ 12 Month: 5 2009

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 855'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE 2" AND 8" ANNULUS TO 470'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED

JUN 08 2009

Remarks: GPS NO. 36. WELL NO.F9G-30 FROM OLD MAP.  
(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I DID NOT observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN