

3 023499

15-207-02170-00-00

To:

API NUMBER

20090015-041

STATE CORPORATION COMMISSION

SE,SW,NE 1/4

Sec/Twp/Rge

S.30-T.26S.-R.17E.

Wichita State Office Bldg. - PLUGGING SECTION

3638 feet from south section line

130 S. Market, Room 2078

1541 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

HEGWALD⁴⁵ NO.F-112

Operator License #

101

County

ALLEN

Operator: STATE OF KANSAS FEE FUND

Well Total Depth

900 feet

Name &

Production Pipe: 2"

Size Feet 900

Address

Surface Casing: 8"

Size Feet 20'

AB oil well

Gas Well

SWD Well/ Input Well

E-8990

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670

Address: 19245 FORD ROAD, CHANUTE, KS. 66720

Company to plug at:

Hour:

8:00A.M.

Day:

15

Month:

5

2008

Plugging proposal received from: CLAYTON TITEL

Company Name:

KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were:

THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 900' THAT HAD BEEN

CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO PERFORATE

THE CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

Part

TECHNICIAN

None

X

Operations Completed: Hour:

5:00PM

Day:

15

Month:

5

2009

Actual Plugging Report:

A REAMER WAS RAN INTO THE 2" CASING TO 525' TO

CLEAR THE CASING. THE 2" CASING WAS PERFORATED AT 200' AND AT 500'. 1" PIPE.

WAS RAN INTO THE WELL TO 830'. CEMANT WAS PUMPED INTO THE 1" PIPE UNTIL

CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE 1" PIPE WAS REMOVED.

DISPLACEMENT WAS FILLLED FROM SURFACE.

WAS FILLED FROM SURFACE.

RECEIVED

JUN 08 2009

Remarks: GPS NO. 45. WELL NO.F-112 FROM OLD MAP.

(If additional description is necessary, use BACK of this form.)

KCC WICHITA

I DID NOT observe this plugging.

Signed:

Clayton P. Titel

TECHNICIAN