

To:	API NUMBER	15-133- 01839-00-00		
STATE CORPORATION COMMISSION		NE SE SW	Sec/Twp/Rge	Sec 2 T28S R18E
Wichita State Office Bldg. - PLUGGING SECTION		1101 (GPS)	feet from south section line	
130 S. Market, Room 2078		2839 (GPS)	feet from east section line	
Wichita, Kansas 67202				
TECHNICIAN'S PLUGGING REPORT		Lease/Well#	Austin (Rush)	gps #AUS 01
Operator License # 101		County	Neosho	
Operator: State Of Kansas Fee Fund		Well Total Depth	800 (est)	feet
Name & Austin - Rush Project		Production Pipe:	NA	Size Feet NA
Address		Surface Casing:	8	Size Feet NA
AB oil well XXXXXX Gas Well _____		SWD Well/ Input Well	_____	D & A _____
Other well as hereinafter indicated: _____				
Plugging Contractor: Kepley Well Service				Lic. # 33749
Address: 19245 Ford Road, Chanute, Kansas 66720				
Company to plug at:		Hour: _____	Day: 21	Month: 5 2009
Plugging proposal received from: Mike Kepley				
Company Name: Kepley Well Service		Phone: 620-433-7196		
Were: Wash well to TD and fill from btm to top with portland cement.				
RECEIVED				
SEP 28 2009				
KCC WICH				
Plugging Proposal Received by: John Almond				
TECHNICIAN				
Plugging attended by Agent:		All _____	Part _____	None XXXXXX
Operations Completed: Hour:		_____	Day: 21	Month: 5 2009
Actual Plugging Report: 5-11-09: The well was washed to 15' inside the SC where the 1" pipe hit solid.				
5-15-09: The drill rig was moved to location and the well drilled to 80' thru wood and rocks. At 80', steel was encountered. A mill bit was then used to reach 120' by drilling thru steel. A 1" cement string was lowered to try to wash deeper but could not. The well was pumped full of cement from btm to top thru this cement string. A total of 47 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.				
Remarks: Control # 20090048-001				
(If additional description is necessary, use BACK of this form.)				

Remarks: Control # 20090048-001

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Alan M. Denning
TECHNICIAN