

15-051-22644-0000

FORM CP-2

State of Kansas



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To be filed by Plugging Agent)

Dear Sir:

Mr. Dana Hewett of Emphasis Oil Operations has this date requested permission to plug the following described well:

Operator's Full Name: N-B Co., Inc.

Complete Address: P. O. Box 506, Russell, Ks. 67665

Lease Name: McGuire Well No. #1

Location: SE/SW/NW Sec. 21 Twp. 11 Rge 16 (E) (W)

County: Ellis Total Depth: 3360'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated: \_\_\_\_\_

Mr. Dana Hewett was instructed to plug the well as follows:

8 5/8"-247' s.p. cuc. w/165 sacks common-2% Gel.-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel.-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem with heavy mud between all plugs.

1st plug @720' w/70 sacks cement

2nd plug @ 240' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

Circulated 10 sacks of cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

Very truly yours,

NOV - 9 1981

[Signature]  
CONSERVATION DIVISION  
Wichita, Kansas  
Conservation Division Agent