

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-133- 01850-00-00  
SW NW NE Sec/Twp/Rge 33-28-21E  
4098 (GPS) feet from south section line  
2342 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: State Of Kansas Fee Fund  
Name & Dent/Vanleeuwen Lease Project  
Address \_\_\_\_\_  
AB oil well XXXXXX Gas Well \_\_\_\_\_

Lease/Well# Vanleeuwen GPS #11  
County Neosho  
Well Total Depth 450 (est) feet  
Production Pipe: 2 Size Feet 450(est)  
Surface Casing: 6 Size Feet NA  
SWD Well/ Input Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: \_\_\_\_\_ Hour: \_\_\_\_\_ Day: 26 Month: 11 2008

Plugging proposal received from: Mike Kepley

Company Name: \_\_\_\_\_ Phone: KANSAS CORPORATION COMMISSION

Were: Clean well to TD and then pump full of cement thru cement string.

RECEIVED  
KANSAS CORPORATION COMMISSION  
DEC 29 2008

CONSERVATION DIVISION  
WICHITA, KS

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX

Operations Completed: Hour: \_\_\_\_\_ Day: 26 Month: 11 2008

Actual Plugging Report: A 1" pipe with a reamer was lowered to 415'. The well was then perforated at 250' and 150'. A 1" cement string was lowered to 400' and the well pumped full of cement from btm to top thru this cement string. A total of 21 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control #20080018-038

(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed:

Alan M. Dunning  
TECHNICIAN