

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-133- 01853-00-00
NE SE NE Sec/Twp/Rge 33-28-21E
3454 (GPS) feet from south section line
496 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Dent/Vanleeuwen Lease Project
Address _____
AB oil well _____ Gas Well _____

Lease/Well# Vanleeuwen GPS #28
County Neosho
Well Total Depth 450 (est) feet
Production Pipe: 2 Size Feet 450(est)
Surface Casing: 6 Size Feet NA
SWD Well/ Input Well E-04612.19 D & A _____

Other well as hereinafter indicated: _____
Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720
Company to plug at: _____ Hour: _____ Day: 17 Month: 2 2009

Plugging proposal received from: Mike Kepley
Company Name: _____ Phone: _____

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning
TECHNICIAN
Plugging attended by Agent: All _____ Part _____ None XXXXXX

Operations Completed: Hour: _____ Day: 17 Month: 2 2009

Actual Plugging Report: 250' of polypipe was removed from inside the 2" production pipe. The well was then perforated at 200' and 100'. A 1" cement string was washed to 275' and the well pumped full of cement from btm to top thru this cement string. A total of 20 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control #20080018-055
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

RECEIVED
KANSAS CORPORATION COMMISSION

MAR 04 2009

CONSERVATION DIVISION
WICHITA KS

Signed: Alan M. Dunning
TECHNICIAN