

To: STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER 15-133- 01856-00-00  
SE NW NE Sec/Twp/Rge 33-28-21E  
3995 (GPS) feet from south section line  
1641 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101  
Operator: State Of Kansas Fee Fund  
Name & Dent/Vanleeuwen Lease Project  
Address \_\_\_\_\_  
AB oil well \_\_\_\_\_ Gas Well \_\_\_\_\_

Lease/Well# Vanleeuwen GPS #34  
County Neosho  
Well Total Depth 450 (est) feet  
Production Pipe: 2 Size Feet 450(est)  
Surface Casing: NA Size Feet NA  
SWD Well/ Input Well E-04612.3 D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: \_\_\_\_\_ Hour: \_\_\_\_\_ Day: 2 Month: 1 2009

Plugging proposal received from: Mike Kepley

Company Name: \_\_\_\_\_ Phone: \_\_\_\_\_

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ None XXXXXX  
TECHNICIAN

Operations Completed: Hour: \_\_\_\_\_ Day: 2 Month: 1 2009

Actual Plugging Report: Approx 130' of the poly pipe was removed. The contractor attempted to remove the remaining poly pipe with a special tool but was unable. The drilling rig was then used to reach a depth of 160'. The well was perforated at 125' and 75'. A 1" cement string was run inside the 2" pipe to 160' and the well pumped full of cement. The cement string was removed and the wellhead directly hooked onto. 2.5 bbls of cement was then squeezed and the well shut in with 400 psi. A total of 20 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control #20080018-061  
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

KANSAS CORPORATION COMMISSION Signed:

Alan M. Dunning  
TECHNICIAN

JAN 26 2009  
RECEIVED