

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-133- 01864-00-00
NE SE NW Sec/Twp/Rge 33-28-21E
3867 (GPS) feet from south section line
2970 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Dent/Vanleeuwen Lease Project
Address _____
AB oil well XXXXXX Gas Well _____

Lease/Well# Dent GPS #27
County Neosho
Well Total Depth 450 (est) feet
Production Pipe: 2 Size Feet 450 (est)
Surface Casing: 7 Size Feet NA
SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: _____ Hour: _____ Day: 23 Month: 2 2009

Plugging proposal received from: Mike Kepley

Company Name: _____ Phone: _____

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

TECHNICIAN

Plugging attended by Agent: All _____ Part _____ None XXXXXX

Operations Completed: Hour: _____ Day: 23 Month: 2 2009

Actual Plugging Report: This well appeared to have only SC present, but the location was dug on and found to have a 2" production string. The well was drilled to 30' where the cement was drilled thru. The well was washed on down 200'. The well was perforated at 200' and 100'. The well was then washed to 310' where the pipe hit solid. A 1" cement string was lowered to 310' and the well pumped full of cement from btm to top thru this cement string. A total 54 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: Control #20080018-027

(If additional description is necessary, use BACK of this form.)

MAR 26 2009

CONSERVATION DIVISION
WICHITA, KS

I did not observe this plugging.

Signed:

Alan M. Dunning
TECHNICIAN