

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-133- 01865-00-00
SE SE NW Sec/Twp/Rge 33-28-21E
3329 (GPS) feet from south section line
2776 (GPS) feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: State Of Kansas Fee Fund
Name & Dent/Vanleeuwen Lease Project
Address _____
AB oil well _____ Gas Well _____

Lease/Well# Dent GPS #28
County Neosho
Well Total Depth 450 (est) feet
Production Pipe: 2 Size Feet 450 (est)
Surface Casing: 7 Size Feet NA
SWD Well/ Input Well E-08930.1 D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: Kepley Well Service, LLC. Lic. # 33749

Address: 19245 Ford Road, Chanute, Kansas 66720

Company to plug at: _____ Hour: _____ Day: 23 Month: 2 2009

Plugging proposal received from: Mike Kepley

Company Name: _____ Phone: _____

Were: Clean well to TD and then pump full of cement thru cement string.

Plugging Proposal Received by: Alan M. Dunning

Plugging attended by Agent: All _____ Part _____ Technician XXXXXX

Operations Completed: Hour: _____ Day: 23 Month: 2 2009

Actual Plugging Report: Approx 280' of polypipe that was inside the 2" production pipe, was removed. The well was then perforated at 250' and 150'. A 1" cement string was lowered down the inside of the 2" production pipe to 280'. The well was pumped full of cement from btm to top thru this cement string. The 1" cement string was removed and the wellhead hooked onto so that the well was shut in with 600 psi. A total of 14 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Remarks: Control #20080018-066
(If additional description is necessary, use BACK of this form.)

I did not observe this plugging.

Signed: Alan M. Dunning
TECHNICIAN

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 26 2009
CONSERVATION DIVISION
WICHITA, KS