

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION

KCC WICHITA

Form ACO-1
June 2009
Form Must Be Typed
Form must be Signed
All blanks must be Filled

WELL COMPLETION FORM
WELL HISTORY - DESCRIPTION OF WELL & LEASE

OPERATOR: License # 3728
Name: Roger Kent dba R J Enterprises
Address 1: 22082 NE Neosho Road
Address 2: _____
City: Garnett State: KS Zip: 66032 + 1918
Contact Person: Roger Kent
Phone: (785) 448-6995 or 448-7725
CONTRACTOR: License # 3728
Name: Roger Kent dba R J Enterprises
Wellsite Geologist: n/a
Purchaser: n/a

Designate Type of Completion:
 New Well Re-Entry Workover
 Oil WSW SWD SIOW
 Gas D&A ENHR SIGW
 OG GSW Temp. Abd.
 CM (Coal Bed Methane)
 Cathodic Other (Core, Expl., etc.): _____

If Workover/Re-entry: Old Well Info as follows:
Operator: _____
Well Name: _____
Original Comp. Date: _____ Original Total Depth: _____
 Deepening Re-perf. Conv. to ENHR Conv. to SWD
 Conv. to GSW
 Plug Back: _____ Plug Back Total Depth _____
 Commingled Permit #: _____
 Dual Completion Permit #: _____
 SWD Permit #: _____
 ENHR Permit #: _____
 GSW Permit #: _____
March 12, 2010 March 16, 2010 March 16, 2010
Spud Date or Date Reached TD Completion Date or
Recompletion Date Recompletion Date

API No. 15 - 001-29980-00-00
Spot Description: _____
SW_NW_NE_NE Sec. 10 Twp. 24 S. R. 21 East West
4,755 Feet from North / South Line of Section
1,155 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Allen
Lease Name: Norman Unit Well #: 2-S
Field Name: Davis-Bronson
Producing Formation: Bartlesville
Elevation: Ground: 1034 ft. Kelly Bushing: n/a
Total Depth: 717 ft. Plug Back Total Depth: 705.1 ft.
Amount of Surface Pipe Set and Cemented at: 20 Feet
Multiple Stage Cementing Collar Used? Yes No
If yes, show depth set: _____ Feet
If Alternate II completion, cement circulated from: surface
feet depth to: 705.1 ft. w/ 80 sx cmt.

Drilling Fluid Management Plan
(Data must be collected from the Reserve Pit)
Chloride content: _____ ppm Fluid volume: _____ bbls
Dewatering method used: Drilled with fresh water - air dry
Location of fluid disposal if hauled offsite: _____
Operator Name: _____
Lease Name: _____ License #: _____
Quarter _____ Sec. _____ Twp. 1 S. R. _____ East West
County: _____ Permit #: _____

INSTRUCTIONS: An original and two copies of this form shall be filed with the Kansas Corporation Commission, 130 S. Market - Room 2078, Wichita, Kansas 67202, within 120 days of the spud date, recompletion, workover or conversion of a well. Rule 82-3-130, 82-3-106 and 82-3-107 apply. Information of side two of this form will be held confidential for a period of 12 months if requested in writing and submitted with the form (see rule 82-3-107 for confidentiality in excess of 12 months). One copy of all wireline logs and geologist well report shall be attached with this form. ALL CEMENTING TICKETS MUST BE ATTACHED. Submit CP-4 form with all plugged wells. Submit CP-111 form with all temporarily abandoned wells.

AFFIDAVIT

I am the affiant and I hereby certify that all requirements of the statutes, rules and regulations promulgated to regulate the oil and gas industry have been fully complied with and the statements herein are complete and correct to the best of my knowledge.
Signature: Donna Shanda
Title: Agent Date: July 29, 2010

KCC Office Use ONLY

Letter of Confidentiality Received
Date: _____
 Confidential Release Date: _____
 Wireline Log Received
 Geologist Report Received
 UIC Distribution
ALT I II III Approved by: DJG Date: 8/6/10

Operator Name: Roger Kent dba R J Enterprises Lease Name: Norman Unit Well #: 2-S
 Sec. 10 Twp. 24 S. R. 21 East West County: Allen

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach complete copy of all Electric Wire-line Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Electric Log Submitted Electronically <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No <i>(If no, Submit Copy)</i> List All E. Logs Run: Gamma Ray/Neutron/CCL	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample Name Top Datum See attached log
--	--

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (In O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface		7"		20'	Oil Well		Kol Seal
Production		2-7/8"		705.2'	Oil Well	80	S-5 Gel/Bentonite
							Cottonseed Hulls

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	# Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate <input type="checkbox"/> Protect Casing <input type="checkbox"/> Plug Back TD <input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type Specify Footage of Each Interval Perforated	Acid, Fracture, Shot, Cement Squeeze Record <i>(Amount and Kind of Material Used)</i>	Depth
21 perfs	637.0 - 647.0 ft.		
17 perfs	656.0 - 664.0 ft.		
21 perfs	668.0 - 678.0 ft.		

TUBING RECORD:	Size:	Set At:	Packer At:	Liner Run: <input type="checkbox"/> Yes <input type="checkbox"/> No
----------------	-------	---------	------------	---

Date of First, Resumed Production, SWD or ENHR.	Producing Method: <input type="checkbox"/> Flowing <input type="checkbox"/> Pumping <input type="checkbox"/> Gas Lift <input type="checkbox"/> Other <i>(Explain)</i> _____			
Estimated Production Per 24 Hours	Oil Bbls.	Gas Mcf	Water Bbls.	Gas-Oil Ratio Gravity

DISPOSITION OF GAS: <input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	METHOD OF COMPLETION: <input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <i>(Submit ACO-5)</i> <input type="checkbox"/> Other <i>(Specify)</i> _____	PRODUCTION INTERVAL: _____ _____
---	---	--

R. J. Enterprises
22082 NE Neosho Rd
Garnett, KS 66032

RECEIVED
JUL 30 2010
KCC WICHITA

Norman Unit 2-S

Start 3-12-10

Finish 3-16-10

2	soil	2	
13	sandstone	15	
132	lime	137	
166	shale	303	
21	lime	324	
63	shale	387	
35	lime	422	
42	shale	464	
15	lime	479	
10	shale	489	
6	lime	495	
98	shale	593	
2	lime	595	
35	shale	630	
8	sandy shale	638	
12	oil sand	650	good show
5	bk sand	655	water
9	oil sand	664	good show
3	oil sand	667	water
14	oil sand	681	good show
9	dk sand	690	show
27	shale	717	T.D.

set 20' 7"
ran 705.1' 2 7/8
consolidated cemented
to surface



CONSOLIDATED
Oil Well Services, LLC

REMIT TO
Consolidated Oil Well Services, LLC
Dept. 970
P.O. Box 4346
Houston, TX 77210-4346

MAIN OFFICE
P.O. Box 884
Chanute, KS 66720
620/431-9210 • 1-800/467-8676
FAX 620/431-0012

INVOICE

Invoice # 2333

Invoice Date: 03/17/2010 Terms: 0/30,n/30

Page

R. J. ENTERPRISE
% ROGER KENT
22082 NE NEOSHO RD
GARNETT KS 66032
(785) 448-6995

NORMAN 2-~~85~~
23989
03-16-10

RECEIVED
JUL 30 2010
KCC WICHITA

Part Number	Description	Qty	Unit Price	Total
1126	OIL WELL CEMENT	80.00	16.5000	1320.00
1110A	KOL SEAL (50# BAG)	320.00	.4000	128.00
1118A	S-5 GEL/ BENTONITE (50#)	200.00	.1700	34.00
1105	COTTONSEED HULLS	25.00	.3800	9.50
4402	2 1/2" RUBBER PLUG	2.00	23.0000	46.00

Description	Hours	Unit Price	Total
445 CEMENT PUMP	1.00	900.00	900.00
445 EQUIPMENT MILEAGE (ONE WAY)	60.00	3.55	213.00
515 TON MILEAGE DELIVERY	264.00	1.20	316.80

Parts:	1537.50	Freight:	.00	Tax:	96.86	AR	3064.16
Labor:	.00	Misc:	.00	Total:	3064.16		
Sublt:	.00	Supplies:	.00	Change:	.00		

Signed _____ Date _____