

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Ellis County, Sec. 20 Twp. 11 Rge. 16 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. C W/2 NW SW

Lease Owner Lario Oil and Gas Company

Lease Name Potter Well No. A-1

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date, well completed November 2 19 40

Application for plugging filed November 2 19 40

Application for plugging approved November 4 19 40

Plugging Commenced November 6 19 40

Plugging Completed November 7 19 40

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. T. Alexander

Producing formation Depth to top 3560 Bottom 3566 Total Depth of Well 3566 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8"	1044'	Cemented

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole was filled with mud from 3566' to 1042', a permanent bridge was set at 1042' and cement to 1027', mudded to 14' and cemented to 8' and mudded to surface.

PLUGGING
FILE REC 20-11 R 16 W
BOOK PAGE 122 NE 14

NOV 15 1940
STATE CORP. COMM.
CONSERV. DIV.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lario Oil and Gas Company, Wichita, Kansas.

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Leo Ross

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leo Ross
Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 14 day of November, 1940

My commission expires June 17, 1944

Margaret Brown
Notary Public.

15-051-01171-0000

WELL LOG BUREAU

Union National Bank Bldg., Wichita, Kansas

Lario Oil and Gas Company - #1 Potter.

Ellis County, Kansas.

C W/2 NW SW

Sec. 20-11-16

All figures represent the bottoms of formations penetrated.

Surface Shale	60
Shale and lime rocks	335
Sand	360
Red beds	425
Sand	500
Shale	600
Sand	660
Shale	725
Red bed	800
Red bed and iron	1000
Red bed and shale	1025
Set 8 1/2" Casing	1042
Lime	1060
Shale and red bed	1350
Lime and shale	1380
Shale	1400
Salt	1580
Shale and shells	1650
Lime	1685
Shale and lime	1965
Lime	1975
Shale and shells	2021
Lime	2090
Lime and shale	2120
Shale	2143
Lime and shale	2195
Shale	2223
Shale and shells	2375
Lime and shale	2475
Broken lime	2515
Shale	2567
Broken lime and shale	2698
Shale and lime shells	2776
Lime	3312
Shale	3360
Conglomerate	3390
Conglomerate Shale	3560
Dolomite shale	3566
Total depth	3566

PLUGGING
 FILE SEC 20 11 R 16W
 BOOK PAGE 122 NE 14

I, G. D. Putnam, being first duly sworn on oath, state that I have knowledge of the facts and matter herein presented, and that the same are true and correct.

G. D. Putnam

Subscribed and sworn before me, this 12 day of November, 1940.

NOV 15 340
STATE CORP. CO.
CO. BUREAU, DIV.

Margaret Brown
Notary Public

My commission expires June 17, 1944

