


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Ellis County, Sec. 20 Twp. 11S Rge. 16 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

SW NE NE
Lease Owner Crown Petroleum
Lease Name Potter Well No. #1
Office Address Suite 501 One Twenty Bldg. Wichita, KS
Character of Well (Completed as Oil, Gas or Dry Hole) 67202



Locate well correctly on above
Section Plat

Dry Hole.
Date Well completed 5-27 1981
Application for plugging filed 5-27 1981
Application for plugging approved 5-27 1981
Plugging commenced 5-27 1981
Plugging completed 5-27 1981
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Smith
Producing formation Depth to top Bottom Total Depth of Well 3330
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	937	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- Mud to 960', 55 sx. cement.
- Mud to 270', 40 sx. cement.
- Mud to 40', 10 sx. cement.
- 5 sx. cement in rathole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor White & Ellis Drilling, Inc.
401 E. Douglas Suite 500 Wichita, Ks. 67202

STATE OF Kansas COUNTY OF Sedgwick, ss.
Ernest Sifford (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Ernest Sifford
401 E. Douglas #500 Wichita, Ks. 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of June 1981

My commission expires April 6, 1985

RECEIVED
Gloria James
Gloria James Notary Public.
JUN 19 1981

CONSERVATION DIVISION
Wichita, Kansas

15-051-22211-0000

DRILLERS LOG

OPERATOR: Crown Petroleum Suite 501 One Twenty Bldg. Wichita, Ks. 67202

CONTRACTOR: White & Ellis Drilling, Inc., Box 448, El Dorado, Kansas 67042

Lease Name: Potter Well No. #1

Sec. 20 T. 11S R. 16W Spot SW NE NE

County: Ellis State: Kansas Elevation:

Casing Record:

Surface: 8 5/8 @ 937' with 425 Sxs.

Production: @ with Sxs.

Type Well: D & A Total Depth 3330'

Drilling Commenced: 5-16-81 Drilling Completed 5-27-81

Formation	From	To	Tops
Cellar	0	5	Kansas City 2980
Sand	5	70	
Sandy Shale	70	466	
Sandy Shale, Shale, Lime	466	1545	
Shale, Lime	1545	1955	
Sandy Shale, Lime	1955	2305	
Shale, Lime	2305	2645	
Lime, Shale	2645	2866	
Shale, Lime	2866	2980	
Lime	2980	3065	
Shale, Lime	3065	3075	
Lime	3075	3270	
Conglomerate	3270	3320	
Lime, Shale	3320	3330	

RECEIVED
STATE CORPORATION COMMISSION

JUN 15 1981

COMPLETION RECORD

Liner Record: Size From To CONSERVATION DIVISION

Cementing Record: Sacks Wichita, Kansas

Perforating Record:

Formation	Perforated Interval	Number Shots

Initial Production:

Electric Log	Type and Depths Covered