

15-051-03668-0001

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 COLORADO DERRY BUILDING  
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

Drilled prior to 1967-  
API NUMBER N/A

LEASE NAME Potter A SWD

WELL NUMBER #3

SPOT LOCATION NW NW SE/4

SEC. 20 TWP. 11 RGE. 16 W (E) OR (W)

COUNTY Ellis

DATE WELL COMPLETED 1/10/58

PLUGGING COMMENCED 9/20/83

PLUGGING COMPLETED 9/22/83

LEASE OPERATOR Mobil Oil Corporation

ADDRESS P. O. Box 5444  
Denver, CO 80217

PHONE #(303) 298-2696 OPERATORS LICENSE NO. 5208

CHARACTER OF WELL SWD  
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Hays, KS

IS ACO-1 FILED?                      IF NOT, IS WELL LOG ATTACHED?                     

PRODUCING FORMATION Lower Arbuckle DEPTH TO TOP 3435' BOTTOM 3626' T.D. 3626'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS                      CASING RECORD                     

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				5 1/2"	3435'	None

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Pumped 75 sacks cement down 8 5/8" surface pipe, communicated through holes to 5 1/2" csg. Hooked up to 5 1/2" csg. Pumped 325 sacks cement down csg. Would not pressure up. Let cement set 2 days. Pumped 120 sacks, cement circulated to surface via 8 5/8" surface csg. Shut surface csg. in, pressured 5 1/2" to 500 psi. Shut well in. P&A complete. Used total of 500 sacks 50/50 Pozmix w/6% gel, 3% calcium chloride.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Halliburton LICENSE No. 5287  
ADDRESS Hays, Kansas


STATE OF Colorado COUNTY OF Denver, SS.

C. J. Park (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) C. J. Park C. J. Park  
P. O. Box 5444  
(ADDRESS) Denver, CO 80217

SUBSCRIBED AND SWORN TO BEFORE ME THIS 10 DAY OF November 1983

Judith R. Olson  
NOTARY PUBLIC



RECEIVED  
STATE CORPORATION COMMISSION  
NOV 14 1983  
CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-4  
REVISED 06-83