

10-23-88

1 120155

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 203-20,088-0000

SW SE SE, SEC. 32, T 19 S, R 36 W/E

330 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5916

Lease Name F.L. Hart Well # 1

Operator: Conoco Inc.

County Wichita 170.63

Name & Address 3817 N.W. Expressway

Well Total Depth 5250 feet

Oklahoma City, OK 73112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Service Drilling License Number 5987

Address Box 5320, Borger, TX 79007

Company to plug at: Hour: 10:30 a.m. Day: 23 Month: 10 Year: 19 88

Plugging proposal received from Otie Clark

(company name) Service Drilling (phone) 806-273-7535

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite top 2283'

1st plug at 4650' with 30 sx cement, 2nd plug at 2300' with 50 sx cement,

3rd plug at 1400' with 50 sx cement, 4th plug at 800' with 50 sx cement,

5th plug at 400' with 50 sx cement, 6th plug at 40' with 10 sx cement,

7th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:45 p.m. Day: 23 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 4650' sx cement,

2nd plug at 2300' with 50 sx cement,

3rd plug at 1400' with 50 sx cement,

4th plug at 800' with 50 sx cement,

5th plug at 400' with 50 sx cement,

6th plug at 40' with 10 sx cement, 7th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

(SEE / did not) observe this plugging.

DATE 10-31-88

Signed Duane Rankin (TECHNICIAN)

INV. NO. 22846 DEC 7 1988

10-23

JAN 25 1989

FORM CP-2/3 Rev. 01-84

INVOICED

Signature

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date September 30, 1988 month day year

API Number 15- 203-20,088-0000

OPERATOR: License # 5916. Name Conoco Inc. Address 3817 N.W. Expressway City/State/Zip Oklahoma City, OK 73112 Contact Person Vernon H. Goodwin Phone (405) 948-3278

SW. SE. SE. Sec. 32. Twp. 19. S, Rg. 36. Ft. from South Line of Section 330. Ft. from East Line of Section 990.

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet County Wichita

CONTRACTOR: License # Being Bid. Out. Name Service Drilling City/State Boyer Tex 800-273-7573

Lease Name F. L. HART Well # 1 Ground surface elevation 3280 feet MSL

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield X Mud Rotary Gas Inj Pool Ext Air Rotary OWWO X Expl X Wildcat Cable

Municipal well within one mile: Depth to bottom of fresh water 100' Depth to bottom of usable water 1200'

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Surface pipe by Alternate 1 X Surface pipe planned to be set 300' Conductor pipe required Projected Total Depth 5250' Formation Mississippi St. Louis

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications. Date 8-11-88 Signature of Operator or Agent Title Supervisor-Regulatory

For KCC Use: Conductor Pipe Required 200 feet per Alt. X 2 This Authorization Expires 2-15-89 Approved By 8-15-88

EFFECTIVE DATE: 8-20-88 SPUD 10-8-88 11 PM 335 8/8

SW SE. SE. Sec. 32. Twp. 19. S, Rg. 36. East West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

- 1st plug @ 4908-4858' feet depth with 30. Class A.
2nd plug @ 1500-1450' feet depth with 30. Class A.
3rd plug @ 1250-1200' feet depth with 30. Class A.
4th plug @ 620-570' feet depth with 30. Class A.
5th plug @ 350-250' feet depth with 45. Class A.
(2) Rathole with 20. Class A.
6th Plug @ 50-0' with 15 sx. Class A

PUSHER Otie Clark TD 5250 FORMATION SURFACE PIPE 8 7/8 @ 335 ANHYDRITE 2283 ELEVATION STARTING TIME & DATE 10-23-88 10:30 AM COMPLETION TIME & DATE 3:45 PM 10-23-88 1st PLUG @ 2300 FT. W/ 50 SX 2nd PLUG @ 1900 FT. W/ 50 SX 3rd PLUG @ 800 FT. W/ 50 SX 4th PLUG @ 400 FT. W/ 50 SX 5th PLUG @ 40 FT. W/ 15 SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ SX WATER WELL PLUGGED W/ SX CEMENT COMPANY AMCO TECHNICALIAN R...

RECEIVED STATE CORPORATION COMMISSION OCT 27 1988 CONSERVATION DIVISION Wichita, Kansas