

6 062192

7-13

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-1167-19312-0000 D 2,573

SE SW NW SEC. 33, T 15 S, R 12 W/E
2970 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6883

Lease Name Grizzell Well # 4
County Russell

Operator: Robinowitz Oil Company
Name &

109.36

Address 7130 S. Lewis #910

Well Total Depth 3365 feet

Tulsa, Ok. 74136

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 427

Abandoned Oil Well _____ Gas Well _____ Input Well xx SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling Inc. License Number 6050

Address Box 347 Chase, Ks. 67524

Company to plug at: Hour 9:00AM Day: 13 Month: July Year: 19 90

Plugging proposal received from Darrell Kelso

(company name) Kelso Casing Pulling Casing (phone) 316-938-2943

were: Order 100 sks common 300 sks 60/40 poz 8% gel 10 sks hulls.

Plugging Proposal Received by Gilbert G. Scheck
(TECHNICIAN)

Plugging Operations attended by Agent?: All xx Part _____ None _____

Operations Completed: Hour: 11:00PM Day: 13 Month: July Year: 19 90

ACTUAL PLUGGING REPORT 8 5/8 set at 427 w/225 sks. 5 1/2 set at 3316 w/125 sks.

Open hole 49'. pumped in 5 1/2 100 sks common followed w/100 sks 60/40 poz 8% gel followed w/5 sks hulls in 175 sks cement w/600 psi.

8 5/8 25 sks cement w/300 psi.

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1990

08-17-90

Remarks: By Allied. Ran line to 3000.
(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

Signed Gilbert G. Scheck
(TECHNICIAN)
Gilbert G. Scheck

INVOICED

DATE: 8-24-90

INV. NO. 290513