

10-13

6 090423

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 051-24,617  
NE , SEC. 31 , T 11 S, R 20 W/E  
2970 feet from S section line  
1850 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4973

Lease Name Hubbs B Well # 1

Operator: Vantage Petroleum Inc.

County Ellis 128.38

Name & Address Box 553

Well Total Depth 3950 feet

Great Bend, Ks. 67530-0553

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well Gas Well Input Well SWD Well U&A x

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address Wichita, Ks.

Company to plug at: Hour: Day: 11 Month: Oct Year: 19 89

Plugging proposal received from Bill Ayres

(company name) Red Tiger Drilling Co. (phone)

were: Order 205 sks 60/40 poz 6% gel and 8 5/8" wiper plug. Spot all plugs through drill pipe w/heavy mud between all plugs.

Plugging Proposal Received by Edwin A. Schumacher (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 9:00 AM Day: 13 Month: Oct Year: 19 89

ACTUAL PLUGGING REPORT  
1st plug 3850' w/20 sks  
2nd plug 1680' w/20 sks  
3rd plug 935' w/100 sks  
4th plug 315' w/40 sks  
5th plug 40' wiper plug and 10 sks  
15 sks in rathole

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 14 1989  
CONSERVATION DIVISION  
WICHITA, KANSAS

Remarks: Elevation 2233' Anhydrite 1656' Arb Yes Halliburton

(If additional description is necessary, use BACK of this form.)

I (did not) observe this plugging.

DATE 11-17-89

Signed Edwin A. Schumacher (TECHNICIAN)

INV. NO. 26498

10-13 DEC 15 1989

FEB 09 1990