

4-041807

E-23,529

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

10-3

API Number: 15-051-24,599 - 0000

NE NW SE /4 SEC. 31, 11 S, 20 W
2310 feet from S section line
1650 feet from E section line

Operator license# 3613

Lease: Hubb Well # 2

Operator: Hallwood Petroleum, Inc.

County: Ellis 126.68

Address: 4582 S. Ulster St. Parkway
Suite #1700
Denver, Colorado 80237

Well total depth 3898 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 261 feet
w/200 sxs.cmt.

Aband. oil well, Gas well, Input well X, SWD, D & A

Plugging contractor: Halliburton Cementing License# -

Address: Hays, Kansas 67601

Company to plug at: Hour: 9:00 A.M. Day 3 Month: October Year 1996

Plugging proposal received from: Aven Weaverling

Company: Hallwood Petroleum, Inc. Phone: 303-850-6257

Were: 5 1/2" casing set at 3898' w/275 sxs cement. Perf. at 3816' - 3833'. Anhy. at 1648' with 500 sxs. T.O.C. 2750'.
Ordered 225 sxs 60/40 pozmix - 10% gel with 1/4# F.C. plus 500# hulls - 14 sxs gel.

Plugging Proposal Received by: Dennis L. Hamel

Plugging operations attended by agent? All [X], Part [], None []

Completed: Hour 10:30 A.M., Day 3, Month: October, Year: 1996

Actual plugging report: R.U. Cementers to squeeze 5 1/2" casing as follows: 25 sxs cement with 200# hulls, followed with 14 sxs gel, followed with 200+ sxs cement with 300# hulls. 8 5/8" S.P. - squeezed 10 sxs cement. Max. P.S.I. 3000#.

Remarks:

Condition of casing(in hole): GOOD BAD X Anhy.plug: YES X NO
Bottom plug(in place): YES, CALC X, NO Dakota plug: YES X, NO
Plugged through TUBING, CASING X Elevation: GL

I did [X] / did not [] observe the plugging. 09-19-96

Dennis L. Hamel (agent)

Form CP-2/3

INVOICED
DATE OCT 17 1996
KANSAS CORP COMM RECEIVED
INV. NO. 46703