

To: 6 031274
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-2
API NUMBER 15-195-20144-0000

SE NE NE, SEC. 36, T 11 S, R 21 W/EX

4290 feet from S section line

330 feet from E section line

Lease Name Huck Well # B-1

County Trego 126.39

Well Total Depth 3889 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 215

TECHNICIAN'S PLUGGING REPORT

Operator License # 4655

Operator: BHP Pet American Inc.

Name & Address

5555 NW Grand Blvd. #200

Oklahoma City, Ok. 73112

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Chase, Ks.

Company to plug at: Hour: AM Day: 2 Month: August Year: 19 89

Plugging proposal received from Bill Fulls through Gib Scheck KCC

(company name) Kelso (phone) _____

were: 8 5/8" set at 215 cwc 4 1/2" set at 3879' w/125 sks. PBTD 3885.

Perfs 3583' - 3605'. This well was squeezed in Dakota area with no records only

5" stretch info from landowner. Bridge at 2370' w/40' of sand w/4 sks common cement

on sand. Order 175 sks 65/35 poz 10% gel 200# hulls. Halliburton Cement Co.

Wellbrock water.

Plugging Proposal Received by _____ (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:00 AM Day: 2 Month: August Year: 19 89

ACTUAL PLUGGING REPORT Sanded bottom to 3530' w/4 sks common cement on sand w/bailer.

Couldn't pull any pipe. Shot at 903' and squeezed casing and annulus. 4 1/2" 75 sks

w/200# hulls at 200 psi on vac. 8 5/8" squeezed w/100 sks to 200 psi. Closed in at 200

psi. Kelso Redi mixed Well and cleaned up location.

RECEIVED
STATE CORPORATION COMMISSION

AUG 17 1989

Remarks: _____

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow

INVOICED
I (did not) observe this plugging.

DATE 8-21-89

INV. NO. 25684